

18 Summary of Mitigation and Residual Impacts

18.1 Introduction

Mitigation describes the measures proposed in order to avoid, reduce and where practicable remedy significant adverse effects. It is also a means by which decisions about a Proposed Project are modified to avoid, reduce or remedy the adverse environmental effects that are identified.

Mitigation measures have been incorporated into the design of the Proposed Project and will be applied during the construction and operation of the Proposed Project. A summary of these mitigation measures is included in the following section. The mitigation measures for both the construction and operational phases are detailed as appropriate. All mitigation measures are based on the Proposed Project as described in Chapter 4, '*Proposed Project Description*'. Individual chapters of the EIS should be referred to for context and detail.

The Contractor appointed to construct the Proposed Project will be required to compile and maintain a Construction Management Plan. This plan will also incorporate the following documents:

- Construction and Environmental Management Plan (CEMP). An outline CEMP is provided in **Appendix 4.1** of this EIS;
- Construction and Demolition Waste Management Plan, refer to Chapter 13, '*Resource and Waste Management*';
- Construction Traffic Management Plan, refer to Chapter 6, '*Traffic and Transportation*'.

18.2 Summary of Mitigation Measures

18.2.1 Traffic and Transportation

18.2.1.1 Construction Phase

General Construction Traffic Strategy

Construction traffic will be limited to certain routes and times of day, with the aim of keeping disruption to existing traffic and public transport to a minimum. To minimise disruption to the local areas, construction traffic volumes will be managed through the following measures which include:

- During peak hours, ancillary, maintenance and other site vehicles movements will be discouraged.
- Daily construction programmes will be planned to minimise the number of disruptions to surrounding streets by staggering HGV movements to avoid site queues.
- No car parking will be provided on site for staff.

- The Contractor will be required to promote travel by sustainable modes of transport. A framework mobility management plan is presented later in this section.

Hours of Working

Construction operations on site will generally be between the hours of 07:00 and 18:00, Monday to Friday, and 08:00 to 14:00 on Saturdays. Similarly, deliveries of materials to site will generally be between the hours of 07:00 and 18:00, Monday to Friday, and 08:00 to 14:00 on Saturdays. However, it is acknowledged that works outside of these hours will be required on occasion. Any works proposed outside the core site hours will be agreed in advance with Dublin City Council.

The construction shift times will ensure any staff travelling to the site by car will have limited impact on the peak periods of 08:00-09:00 in the morning and 17:00-18:00 in the evening as it is envisaged most construction staff will arrive to work before 08:00 in the morning and leave after 18:00 in the evening.

Construction Traffic Management Plan

As part of the construction works the appointed Contractor shall prepare a Construction Traffic Management Plan (CTMP) which will outline their approach to the Proposed Project and detail potential impacts for the public road system. This will include provision of transport facilities and encouragement of car sharing for staff. It will also include measures to mitigate any potential noise and air quality impacts resulting from construction activities, namely from traffic movements in and out of the site.

The CTMP will provide details of intended construction practice for the development, including:

- Location of the site and materials compound(s) including area(s) identified for the storage of construction refuse.
- Location of areas for construction site offices and staff facilities.
- Details of site security fencing and hoardings.
- Details of pedestrian routes through College Green.
- Details of the timing and routing of construction traffic to and from the construction site and associated directional signage, to include proposals to facilitate the delivery of abnormal loads to the site.
- Measures to obviate queuing of construction traffic on the adjoining road network.
- Measures to prevent the spillage or deposit of clay, rubble or other debris on the public road network.
- Alternative arrangements to be put in place for pedestrians and vehicles in the case of the closure of any public road or footpath during the course of site development works.
- Details of appropriate mitigation measures for noise, dust and vibration, and monitoring of such levels.

within the context of the surrounding urban fabric, it is not warranted to provide any long term forms of mitigation.

Only during the construction phase is mitigation considered necessary in respect of townscape and visual issues. These relate to ensuring that College Green does not become a place that will be avoided by locals and visitors during the 12-18 month construction period. Effects that could give rise to this situation relate to perceived danger, congestion, way-finding confusion, scattering of dust and debris and overall visual clutter and disharmony. Mitigation to reduce these adverse construction related effects is principally the concern of the Construction and Environmental Management Plan (an outline is provided in **Appendix 4.1**). This will include the form of site hoarding, which in this instance should be solid and well constructed to reduce visibility of the on-going works and will also reduce the noise and dust emissions from the site. It is proposed that the solid hoardings will also include images of the future plaza as this can remind those affected of the long-term benefit of the temporary works. Pedestrian and cycle movement areas will be generous in dimension and clearly presented in terms of directional movement to avoid confusion. Areas outside of the site hoarding will also be kept clear of dust and debris.

18.2.7 Soils, Geology, Hydrogeology and Hydrology

A project-specific Construction Management Plan (CMP) will be prepared and submitted to the planning authority for approval. It will be maintained by the Contractor for the duration of the construction phase. The CMP will cover all potentially polluting activities and include an emergency response procedure. All personnel working on the site will be trained in the implementation of the procedures.

As a minimum, the CMP manual for the Proposed Project site will be formulated in consideration of the standard best practice. The CMP will include a range of site specific measures which will include:

- Earthworks operations shall be carried out such that surfaces shall be designed with adequate falls, profiling and drainage to promote safe run-off and prevent ponding and flooding.
- Run-off will be controlled to minimise the water effects in outfall areas.
- Good housekeeping (site clean-ups, use of disposal bins, etc.) on the site project.

In order to prevent the accidental release of hazardous materials (fuels, cleaning agents, etc.) during construction site activity, all hazardous materials will be stored within secondary containment designed to retain at least 110% of the storage contents. Temporary bunds for oil/diesel storage tanks will be used on the site during the construction phase of the Proposed Project. Safe materials handling of all potentially hazardous materials will be emphasised to all construction personnel employed during this phase of the Proposed Project.

Mitigation during the construction phase will include implementing best practice during excavation works to avoid sediment running into the drainage system which discharges to the River Liffey.

18.2.8 Resource and Waste Management

A Construction and Demolition Waste Management Plan (CDWMP) will be required to be developed by the Main Contractor(s) following appointment and prior to commencing works on site.

The CDWMP will address waste generation and arrangements made for prevention, reuse, recycling disposal and collection of recyclables and wastes. It will be prepared in line with the *DoEHLG Best Practise Guidelines on the Preparation of Waste Management Plans for Construction & Demolition Projects*.

The following is an indicative list on the content of a CDWMP:

- Description of the Proposed Project;
- Wastes arising including proposals for minimisation/reuse/recycling;
- Procedures for prevention, reuse and recycling of wastes;
- Estimated cost of waste management;
- Roles including training and responsibilities for C&D Waste;
- Procedures for education of workforce and plan dissemination programme
- Record keeping procedures;
- Waste collectors, recycling and disposal sites including copies of relevant permits or licences; and
- Waste auditing protocols.

Using the information identified in this section and the outline Construction Environmental Management Plan in **Appendix 4.1** as a basis the Contractor will be required to develop, implement and maintain a CDWMP for the construction phase of the Proposed Project.

In addition to the inherent design measures during the construction phase the following mitigation measures are proposed:

- The Contractor will minimise waste disposal so far as is reasonably practicable;
- Waste from the Proposed Project will be transported by authorised waste collectors in accordance with the Waste Management (Collection Permit) Regulations, 2007 as amended;
- Waste from the Proposed Project will be delivered to authorised waste facilities in accordance with the Waste Management Acts 1996 as amended;
- Source Segregation: Where possible metal, timber, glass and other recyclable material will be segregated during construction works and removed off site to a permitted/licensed facility for recycling. Waste stream colour coding, and photographs of wastes to be placed in each container as required, will be used to facilitate segregation. Where waste generation cannot be avoided this will maximise the quantity and quality of waste delivered for recycling and facilitate its movement up the waste hierarchy away from landfill disposal and reduce its environmental impact;

- **Material Management:** ‘Just-in-time’ delivery will be used so far as is reasonably practicable to minimise material wastage;
- **Supply Chain Partners:** The Contractor will engage with the supply chain to supply products and materials that use minimal packaging, and segregate packaging for reuse; and
- **Waste Auditing:** The Contractor will record the quantity in tonnes and types of waste and materials leaving site during the construction phase.

18.2.9 Material Assets: Utilities

The Contractor will be obliged to put measures in place to ensure that there are no interruptions to existing services and all services and utilities are maintained unless this has been agreed in advance with the relevant service provider and local authority.

All works in the vicinity of utilities apparatus will be carried out in ongoing consultation with the relevant utility company and/or local authority and will be in compliance with any requirements or guidelines they may have.

Where new services are required, the Contractor will apply to the relevant utility company for a connection permit where appropriate, and will adhere to their requirements.

18.2.10 Material Assets: Land Use and Property

18.2.10.1 Construction Phase

During the construction phase, site management measures including the provision of high quality hoarding and proactive communication with business and public regarding phasing, extent and duration of works will be carried out. Access to all properties will be maintained during the construction phase. Signage will be provided as necessary.

18.2.10.2 Operational Phase

No mitigation measures are required as it is expected that the Proposed Project will have a positive impact on land use and property.

The management of land use is a function of the Dublin City Council’s planning department in accordance with the policies of the Dublin City Development Plan 2016-22.

The careful management of proposals for change of use in a coherent manner is likely to complement the investment in the plaza is a very important role to mitigate negative impacts arising from value and use changes in property beside the plaza.

The taxi rank will be removed at College Green (five spaces). The taxi parking facility at Foster Place is to be removed entirely. It is proposed to introduce a taxi rank on the outbound lane on Dame Street, east of South Great George’s Street and west of Trinity Street. Adjoining this would be 35 metres of loading bay which would be a night time taxi rank. A loading bay will act as night time taxi rank, is proposed for the East side of Trinity Street just prior to the junction of St Andrew’s Street.

A loading bay which will act as night time taxi rank, is proposed for the west side of Church Lane. The impact on property and land use from these measures is considered neutral.

18.2.11 Socio-Economics

18.2.11.1 Construction Phase

This assessment, has determined that the negative impact on businesses during the construction will be of slight to moderate negative significance. A broad range of mitigation measures will be implemented for the construction of the Proposed Project.

Mitigation measures for traffic/pedestrians relate primarily to maintaining access to businesses, which will minimise disruption during the construction phase. Changes to traffic, public transportation and access to the city core will be clearly communicated to the resident and visiting public.

The capacity for business to be serviced on street, and receive deliveries in limited periods in the day would mitigate the socioeconomic impact of the proposal.

Alternative access arrangements for private cars and buses will mitigate the impact of direct access through College Green.

Mitigation measures will be introduced to minimise disruption during construction to businesses and visitors in terms of air and noise, refer to Chapters 7 and 8. The bus route reorganisation is obliged to meet air quality standards so that businesses and dwellings in the central area are not negatively affected by the re-organisation, refer to Chapter 7, '*Air Quality and Climate Factors*'.

Luas Cross City works will be completed before construction commences on the site to ensure that north-south access by bus and taxis is available. Taxi ranks will be re-located on adjoining streets with no net loss in parking spaces.

Changes to operation of services will be clearly communicated to customers and visitors, including on-street signage.

18.2.11.2 Operational Phase

During the operational phase, the most important mitigation measures refer to the management and maintenance of the space. In order to sustain a positive impact on the economy of the city centre, a high level of street cleaning measures will be implemented and a policing presence maintained to ensure that there is a strong sense of a safe and secure space, where anti-social behaviour is controlled. As a public authority Dublin City Council engages with the Gardaí on a regular basis and has the capacity to work with Gardaí directly and in policing forums to manage the safety and security of the space.

Taxi ranks will be re-located on nearby adjoining streets (Dame Street, east of South Great George's Street and west of Trinity Street) with no net loss in parking spaces. Dublin City Council as the roads authority is empowered to provide these alternative spaces.

Luas Cross City works will be completed before construction commences on the site to ensure that north-south access by bus and taxis is available.

18.3 Summary of Residual Impacts

18.3.1 Traffic and Transportation

During construction, the Proposed Project will result in a temporary increase in traffic volumes along Dame Street and approach routes to the construction site. However, these increases will be negligible and not result in any material impact on the operation of the local road network.

Once operational, the College Green Project will improve pedestrian, cyclist and public transport mobility through the centre of the city. The Proposed Project will result in changes to traffic flows on a number of road links within the city centre. The residual impacts in terms of traffic are considered further in the Chapter 7 '*Air Quality and Climate Factors*' and Chapter 8 '*Noise and Vibration*' which are the direct environmental impacts as a result of increased traffic.

18.3.2 Air Quality and Climate

18.3.2.1 Construction phase

When the dust minimisation measures detailed in the mitigation section of this chapter are implemented, fugitive emissions of dust from the site will be insignificant and pose no nuisance at nearby receptors.

Due to the size and nature of the construction activities, CO₂ and N₂O emissions during construction will have a negligible impact on climate.

18.3.2.2 Operational phase

The air dispersion modelling assessment has found that the Proposed Project will be beneficial overall in the study area. By 2035 all ground level and first-floor façades will have ambient air quality in compliance with the ambient air quality standards for the do something (and do minimum) scenario.

In relation to 2018, the Proposed Project will improve air quality at significantly more receptors relative to the number of receptors which deteriorate in air quality.

There will however be a period of time, between opening year and 2021, during which a number of first-floor facades are likely to remain above the annual mean NO₂ ambient air quality standard and between opening year and 2024, during which some ground level façades are likely to be in excess of the annual mean NO₂ ambient air quality standard.

However, in the absence of the Proposed Project, the impact on existing ground floor and first-floor façades will be greater with a higher number of receptors experiencing air quality in excess of the annual mean NO₂ limit value for a period of time.

18.3.3 Noise and Vibration

The modelling outputs for the day time 2018 do something (DS) scenario predict an increase of 5% in residential addresses points in the undesirable day time category and a decrease of 2% in residential locations in the desirable category.

The study concludes that when comparing the do minimum (DM) and DS 2018 scenarios for night time, a 5% increase in residential locations in the undesirable band and a slight decrease of approximately 1% in the desirable band is predicted.

At Parliament Street, it is predicted that there will be no difference to noise exposure levels at all address points, for either day or night time.

The modelling outputs for the day time 2035 DS scenario predict an increase of 9% in residential addresses points in the undesirable day time category and a decrease of 3% in residential locations in the desirable category.

The study concludes that when comparing the DM and DS 2035 scenarios for night time, a 1% increase in residential locations in the undesirable band and a slight decrease of approximately 2% in the desirable band is predicted.

At Parliament Street, it is predicted that there will be no difference to noise exposure levels at all address points, for either day or night time.

18.3.4 Biodiversity

There will be no significant impact on biodiversity following the proposed best practice construction management measures and tree replacement.

Construction management measures to prevent impacts on surface water quality which have been described in the EIS will be included in a Construction and Environmental Management Plan (refer to **Appendix 4.1**) to ensure these measures are fully implemented by the Contractor.

There will be no significant residual impacts on surface water quality once these measures have been employed.

18.3.5 Archaeology, Architectural and Cultural Heritage

With regards to the archaeological resource, following the implementation of the mitigations measures, there will be no residual impact on the archaeological resource.

The residual impact of the Proposed Project on architectural heritage will be positive, removing traffic from College Green and allowing it to be a high-quality urban space, with the surrounding buildings and the memorials, all of which are of architectural heritage significance, to become an integral part of the space.

18.3.6 Townscape and Visual

There is no need to mitigate the operational stage of the development as it is deemed to result in positive impacts that will enhance the townscape of College Green and its environs. However, it is considered that if the construction stage mitigation measures to achieve a tidy and orderly site are appropriately implemented, the predicted 'Moderate' significance of visual impact (**Section 11.4.2.2**) will reduce to **Moderate-slight**.

18.3.7 Soils, Geology, Hydrogeology and Hydrology

Upon application of the mitigation measures outlined the magnitude of any impacts both in the construction and operational phase are Negligible as detailed

in **Table 18.1** (see **Appendix 12.1** for definitions). As a result, the significance of all the impacts is Imperceptible.

Table 18.1 - Summary of residual impacts on the identified features of importance

Feature	Soil	Bedrock aquifer classified by the GSI as a Locally Important Aquifer which is productive only in local zones (LI)
Importance	Low	Medium
Justification	Poorly drained soil	Locally important aquifer.
Magnitude	Small adverse	Negligible
Justification	a low risk of pollution to the soils	Results in impact on attribute but of insufficient magnitude to affect either use or integrity
Significance	Imperceptible	Imperceptible
Mitigation measure	Refer to Section 12.8	Refer to Section 12.8
Residual impact	Negligible	Negligible
Justification	Imperceptible	Imperceptible

18.3.8 Resource and Waste Management

Following the implementation of the mitigation, the residual impacts are expected to be as follows:

- The impact of excavation waste is expected to be slight, negative and short-term.
- The impact of construction waste is expected to be imperceptible.
- The impact of operational waste is expected to be imperceptible.

There is considered to be adequate capacity in the region to receive the wastes likely to be generated by the construction and operation of the Proposed Project.

18.3.9 Material Assets: Utilities

Following implementation of mitigation measures outlined above, the residual impact on utility services is considered to be imperceptible.

18.3.10 Material Assets: Land Use and Property

18.3.10.1 Construction Phase

A moderate inconvenience to business deliveries and access will be experienced as a result of the establishment and ongoing use of the construction site. However, the mitigation measures outlined will maintain access arrangements and ensure no significant negative effects arise.

18.3.10.2 Operational Phase

In the long-term the Proposed Project is expected to become one of the core focal points of the city centre, sustaining a permanent positive legacy for the city.

