




- ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND
- NOTES:
1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ARCHITECTURAL AND ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE DUBLIN CITY COUNCIL.
 2. ORTHOPHOSPHATS DATA WAS RECEIVED FROM MURPHY GEOSPATIAL 17.01.2022. ALL CO-ORDINATES ARE IN IRISH TRANSVERSE MERCATOR(ITM)
 3. ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 4. DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 5. ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 6. CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS' NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 7. WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.



AVAILABLE UTILITY
INFORMATION SUGGESTS
THE PRESENCE OF HIGH
VOLTAGE CABLES, GAS
MAINS AND OTHER UTILITY
SERVICES IN THE WORKS
AREA

LEGEND

WORKS AREA - - - - -

FOR TENDER

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish

Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	30.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client	
Comhairle Cathrach Bhaile Átha Cliath Dublin City Council	
Date	Scale
30.04.2025	1:1000@A1 1:2000@A3
Project Code	Originator Code
NTA190002	NTA

Engineering Designer		
AECOM		
Drawn	Checked	Approved
RD	AP	EG
QMS Code	S04.1	

Project Title			
FITZWILLIAM QUAY - LONDONBRIDGE STREET SECTION 1			
Drawing Title			
SITE LOCATION			
Drawing File Name	Sheet Number	Status	Rev
NTA190002-NTA-GEN_KP-S04.1_XX_01-DR-KK-001	1 of 1	B2	P02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY



- ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND
- NOTES:
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ARCHITECTURAL AND ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE DUBLIN CITY COUNCIL.
 - ORTHOPHOSPHATS DATA WAS RECEIVED FROM MURPHY GEOSPATIAL 17.01.2022. ALL CO-ORDINATES ARE IN IRISH TRANSVERSE MERCATOR(ITM)
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS' NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.

- LEGEND:
- EXISTING KERB TO BE RETAINED
 - PROPOSED EXTRUDED CONCRETE SEGREGATION KERB
 - PROPOSED IN-SITU CONCRETE KERB
 - PROPOSED IN-SITU CONCRETE DROPPED TRANSITION KERB
 - PROPOSED EDGING KERB
 - PROPOSED EXTRUDED 30 DEGREE SPLAY KERB WITH 60mm UPSTAND
 - PROPOSED GRANITE KERB, INTEGRATION OF NEW KERBS TO BE AGREED ON SITE WITH DCC.
 - PROPOSED GRANITE DROP KERB, INTEGRATION OF NEW KERBS TO BE AGREED WITH DCC ON SITE.
 - PROPOSED CYCLE RAMP
 - PROPOSED CYCLE FACILITY
 - PROPOSED GRASS VERGE
 - PROPOSED FOOTPATH BUILDOUT
 - PROPOSED BOLLARD
 - EXISTING HERITAGE FEATURE
 - PROPOSED RED / BUFF TACTILE PAVING
 - PROPOSED BUFF CORDUROY TACTILE
 - PROPOSED SPEED RESTRICTION RAMP
 - EXISTING CARRIAGEWAY
 - EXISTING FOOTPATH

- TREE LEGEND:
- TREE STEM
 - NOMINAL ROOT PROTECTION AREA (RPA)
 - ADJUSTED RPA
- NOTE - ROAD MARKINGS ARE SHOWN FOR CLARITY ONLY. PLEASE REFER TO SERIES 1200 FOR DETAILS.

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER

Project Ireland 2040 Building Ireland's Future NTA Údarás Náisiúnta Iompair National Transport Authority © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA. b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings. c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station. d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superseded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed. e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.										<table><tr><th>Rev</th><th>Date</th><th>Drm</th><th>Chk'd</th><th>App'd</th><th>Description</th></tr><tr><td>P01</td><td>22.09.2023</td><td>RD</td><td>AB</td><td>EG</td><td>ISSUED FOR TENDER REVIEW</td></tr><tr><td>P02</td><td>21.12.2023</td><td>GH</td><td>AB</td><td>EG</td><td>ISSUED FOR TENDER REVIEW</td></tr><tr><td>P03</td><td>12.01.2024</td><td>AK</td><td>AB</td><td>EG</td><td>ISSUED FOR TENDER</td></tr><tr><td>P04</td><td>29.04.2025</td><td>RD</td><td>AP</td><td>EG</td><td>ISSUED FOR TENDER</td></tr></table>	Rev	Date	Drm	Chk'd	App'd	Description	P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW	P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW	P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER	P04	29.04.2025	RD	AP	EG	ISSUED FOR TENDER	Client Comhairle Cathrach Bhaile Átha Cliath Dublin City Council	Engineering Designer AECOM	Project Title FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1
Rev	Date	Drm	Chk'd	App'd	Description																																						
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW																																						
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW																																						
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER																																						
P04	29.04.2025	RD	AP	EG	ISSUED FOR TENDER																																						
<table><tr><th>Date</th><th>Scale</th><th>Drawn</th><th>Checked</th><th>Approved</th></tr><tr><td>29.04.2025</td><td>1:200@A1 1:400@A3</td><td>RD</td><td>AP</td><td>EG</td></tr></table>						Date	Scale	Drawn	Checked	Approved	29.04.2025	1:200@A1 1:400@A3	RD	AP	EG	Drawing Title GENERAL ARRANGEMENT	Drawing File Name NTA190002-NTA-SLW_ZZ-S04.1_XX_01-DR-KK-0003	Sheet Number 3 of 5	Status E3	Rev P04																							
Date	Scale	Drawn	Checked	Approved																																							
29.04.2025	1:200@A1 1:400@A3	RD	AP	EG																																							
Project Code NTA190002		Originator Code NTA		QMS Code S04.1																																							

REFER TO PROJECT SPECIFIC STANDARD DETAIL
NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0006

RIVER DODDER

PROPOSED SHARED USE AREA

ACCESS TO UTILITY CABINETS IN
WALL TO BE RETAINED, KERB BUILD
OUT NOT TO EXTEND PAST EITHER

CH-400

ES

Chy

24C 24B 24A 24

1-12,
13-24

POTENTIAL BADGER ACTIVITY. PLEASE
REFER TO THE WORKS REQUIREMENTS FOR
RESTRICTIONS TO WORKS IN THESE AREAS

EXISTING CONCRETE BUILD
OUT TO BE RETAINED

LONDONBRIDGE ROAD

SHARED STREET / MIXED STREET TREATMENT
PROPOSED ON LONDONBRIDGE ROAD
INVOLVING ADDITION OF ROAD MARKINGS ONLY

CH-450

EXISTING FOOTPATH TO BE RETAINED

LONDON BRIDGE

EXTENT OF WORKS

LONDONBRIDGE ROAD

BATH AVENUE



AVAILABLE UTILITY
INFORMATION SUGGESTS
THE PRESENCE OF HIGH
VOLTAGE CABLES, GAS
MAINS AND OTHER UTILITY
SERVICES IN THE WORKS
AREA

FOR TENDER

NOTES:

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ARCHITECTURAL AND ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE DUBLIN CITY COUNCIL.
2. ORTHOPHOSPHATS DATA WAS RECEIVED FROM MURPHY GEOSPATIAL 17.01.2022. ALL CO-ORDINATES ARE IN IRISH TRANSVERSE MERCATOR(ITM)
3. ALL DIMENSIONS TO BE CHECKED BY THE CONTRACTOR ON SITE PRIOR TO COMMENCEMENT OF WORKS.
4. CYCLE DESIGN OFFICE OR DCC TO BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
5. DIMENSIONS OF ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
6. DO NOT SCALE. ALL MEASUREMENTS AND COORDINATES TO BE CHECKED ON SITE.

LEGEND:

- EXISTING KERB TO BE RETAINED
- PROPOSED EXTRUDED CONCRETE SEGREGATION KERB
- PROPOSED IN-SITU CONCRETE KERB
- PROPOSED IN-SITU CONCRETE DROPPED TRANSITION KERB
- PROPOSED EDGING KERB
- PROPOSED EXTRUDED 30 DEGREE SPLAY KERB WITH 60mm UPSTAND
- PROPOSED GRANITE KERB, INTEGRATION OF NEW KERBS TO BE AGREED ON SITE WITH DCC.
- PROPOSED GRANITE DROP KERB, INTEGRATION OF NEW GRANITE DROP KERBS TO BE AGREED WITH DCC ON SITE.
- PROPOSED CYCLE RAMP
- PROPOSED CYCLE FACILITY
- PROPOSED GRASS VERGE
- PROPOSED FOOTPATH BUILDOUT
- PROPOSED BOLLARD
- EXISTING HERITAGE FEATURE
- PROPOSED RED / BUFF TACTILE PAVING
- PROPOSED BUFF CORDUROY TACTILE
- PROPOSED SPEED RESTRICTION RAMP
- EXISTING CARRIAGEWAY
- EXISTING FOOTPATH

TREE LEGEND:

- TREE STEM
- NOMINAL ROOT PROTECTION AREA (RPA)
- ADJUSTED RPA

NOTE - ROAD MARKINGS ARE SHOWN FOR CLARITY ONLY. PLEASE REFER TO SERIES 1200 FOR DETAILS.

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish

Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.


e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	29.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		Engineering Designer AECOM		
Date 29.04.2025	Scale 1:200@A1 1:400@A3	Drawn RD	Checked AP	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1				
Drawing Title GENERAL ARRANGEMENT				
Drawing File Name NTA190002-NTA-SLW_ZZ-S04.1_XX_01-DR-KK-0005	Sheet Number 5 of 5	Status E3	Rev P04	



TREE LEGEND:

- TREE STEM
- NOMINAL ROOT
- PROTECTION AREA (RPA)
- ADJUSTED RPA

LEGEND (CONTINUED):

- TAKE UP OR DOWN EXISTING INSPECTION COVERS AND FRAME, STOP COCK AND STOP / GAS VALVE/ FIRE HYDRANT AND SET ASIDE FOR REUSE AT NEW PROPOSED LEVEL.
- EXISTING INSPECTION CHAMBER COVER TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE.
- EXISTING INSPECTION CHAMBER TO BE PROTECTED IN PLACE AND ITS COVERS TO BE RAISED TO PROPOSED LEVEL.
- EXISTING SIGN POST AND SIGN FACE TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE. REFER TO SIGN SCHEDULE FOR DETAILS.
- EXISTING SIGN POST TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE. EXISTING SIGN FACE TO BE REMOVED AND SET ASIDE FOR REUSE. REFER TO SIGN SCHEDULE FOR DETAILS.
- EXISTING SIGN POST AND SIGN PLATE TO BE REMOVED. AND SET ASIDE FOR REUSE. REFER TO SIGN SCHEDULE FOR DETAILS.
- REFUSE BIN TO BE REMOVED TO STORE FOR RELOCATION
- TAKE UP OR DOWN EXISTING BOLLARD PAVING SLAB AND FOUNDATION AND REMOVE TO STORE
- EXISTING ROAD MARKINGS TO BE REMOVED
- EXISTING MANHOLE TO BE ADJUSTED TO SUIT NEW FINISHED LEVEL AS REQUIRED
- EXISTING ROAD HUMP TO BE REMOVED. REFER TO SERIES 0600 DRAWINGS FOR DETAILS.
- EXISTING VEGETATION TO BE REMOVED TO TIP OFF SITE
- EXISTING HERITAGE FEATURE TO BE PROTECTED IN PLACE
- EXISTING SIGNAL POLE TO BE REMOVED TO STORE, SIGNAL HEADS, DUCTING, AND CHAMBERS TO BE REUSED ON SITE

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

- NOTES:**
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY, THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - THE LOCATION AND DEPTH OF SERVICES TO BE CHECKED ON SITE PRIOR TO COMMENCING ANY WORKS. NO WARRANTY GIVEN AS TO THE ACCURACY OF THE INFORMATION PROVIDED.
 - LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS.
 - THE CONTRACTOR IS TO ENSURE THAT DISTURBANCE TO LOCAL WATER, POWER OR COMMUNICATION SUPPLY MUST BE AVOIDED WHERE POSSIBLE, WHERE UNAVOIDABLE, IT MUST BE KEPT TO A MINIMUM AND PROPERTY OWNERS NOTIFIED.

- LEGEND:**
- TAKE UP OR DOWN EXISTING KERB, BEDDING, AND BACKING TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE
 - TAKE UP OR DOWN EXISTING ANTIQUE GRANITE KERB, BEDDING AND BACKING TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE
 - EXISTING CONCRETE PAVING SLABS FOOTWAY, APPROX 600x600x63mm CONCRETE PAVING SLAB, TO BE REMOVED TO STORE.
 - EXISTING BLOCK PAVING FOOTWAY, APPROX 22x180x80mm CONCRETE BLOCK PAVIORS, AND APPROX 300x200mm RESTRAINING BEAMS TO BE REMOVED TO STORE.
 - EXISTING FOOTPATH TO BE BROKEN OUT AND EXCAVATED TO FORMATION LEVEL MINIMUM OF 250mm CONCRETE SURFACING AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0005'
 - REFER TO SERIES 0700 DRAWINGS FOR PAVEMENT TREATMENTS
 - AREA OF VERGE TO BE EXCAVATED AND STOCKPILED ON SITE FOR REUSE

FOR TENDER

Disclaimer

a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titleblock. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040
Building Ireland's Future


NTA
Údarás Náisiúnta Iompair
National Transport Authority

Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Comhairle Cathrach
Bhaile Átha Cliath
Dublin City Council

Date	28.04.2025	Scale	1:200@A1 1:400@A3	Drawn	RD	Checked	AP	Approved	EG
Project Code	NTA190002	Originator Code	NTA	QMS Code	S04.1				

Project Title	FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title	SITE CLEARANCE			
Drawing File Name	NTA190002-NTA-SPW_SC-S04.1_XX_01-DR-KK-0002	Sheet Number	2 of 5	Status
				E3
				Rev
				P04



TREE LEGEND:

- TREE STEM
- NOMINAL ROOT
- PROTECTION AREA (RPA)
- ADJUSTED RPA

LEGEND (CONTINUED):

- TAKE UP OR DOWN EXISTING INSPECTION COVERS AND FRAME, STOP COCK AND STOP / GAS VALVE/ FIRE HYDRANT AND SET ASIDE FOR REUSE AT NEW PROPOSED LEVEL.
- EXISTING INSPECTION CHAMBER COVER TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE.
- EXISTING INSPECTION CHAMBER TO BE PROTECTED IN PLACE AND ITS COVERS TO BE RAISED TO PROPOSED LEVEL.
- EXISTING SIGN POST AND SIGN FACE TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE. REFER TO SIGN SCHEDULE FOR DETAILS.
- EXISTING SIGN POST TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE. EXISTING SIGN FACE TO BE REMOVED AND SET ASIDE FOR REUSE. REFER TO SIGN SCHEDULE FOR DETAILS.
- EXISTING SIGN POST AND SIGN PLATE TO BE REMOVED. AND SET ASIDE FOR REUSE. REFER TO SIGN SCHEDULE FOR DETAILS.
- REFUSE BIN TO BE REMOVED TO STORE FOR RELOCATION
- TAKE UP OR DOWN EXISTING BOLLARD PAVING SLAB AND FOUNDATION AND REMOVE TO STORE
- EXISTING ROAD MARKINGS TO BE REMOVED
- EXISTING MANHOLE TO BE ADJUSTED TO SUIT NEW FINISHED LEVEL AS REQUIRED
- EXISTING ROAD HUMP TO BE REMOVED. REFER TO SERIES 0600 DRAWINGS FOR DETAILS.
- EXISTING VEGETATION TO BE REMOVED TO TIP OFF SITE
- EXISTING HERITAGE FEATURE TO BE PROTECTED IN PLACE
- EXISTING SIGNAL POLE TO BE REMOVED TO STORE, SIGNAL HEADS, DUCTING, AND CHAMBERS TO BE REUSED ON SITE

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

- NOTES:**
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY, THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - THE LOCATION AND DEPTH OF SERVICES TO BE CHECKED ON SITE PRIOR TO COMMENCING ANY WORKS. NO WARRANTY GIVEN AS TO THE ACCURACY OF THE INFORMATION PROVIDED.
 - LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS.
 - THE CONTRACTOR IS TO ENSURE THAT DISTURBANCE TO LOCAL WATER, POWER OR COMMUNICATION SUPPLY MUST BE AVOIDED WHERE POSSIBLE, WHERE UNAVOIDABLE, IT MUST BE KEPT TO A MINIMUM AND PROPERTY OWNERS NOTIFIED.

LEGEND:

- TAKE UP OR DOWN EXISTING KERB, BEDDING, AND BACKING TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE
- TAKE UP OR DOWN EXISTING ANTIQUE GRANITE KERB, BEDDING AND BACKING TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE
- EXISTING CONCRETE PAVING SLABS FOOTWAY, APPROX 600x600x63mm CONCRETE PAVING SLAB, TO BE REMOVED TO STORE.
- EXISTING BLOCK PAVING FOOTWAY, APPROX 22x180x80mm CONCRETE BLOCK PAVIORS, AND APPROX 300x200mm RESTRAINING BEAMS TO BE REMOVED TO STORE.
- EXISTING FOOTPATH TO BE BROKEN OUT AND EXCAVATED TO FORMATION LEVEL MINIMUM OF 250mm CONCRETE SURFACING AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0005'
- REFER TO SERIES 0700 DRAWINGS FOR PAVEMENT TREATMENTS
- AREA OF VERGE TO BE EXCAVATED AND STOCKPILED ON SITE FOR REUSE

FOR TENDER

Disclaimer

a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titleblock. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken as appropriate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040
Building Ireland's Future

NTA
Údarás Náisiúnta Iompair
National Transport Authority

Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Comhairle Cathrach
Bhaile Átha Cliath
Dublin City Council

Date	28.04.2025	Scale	1:200@A1 1:400@A3	Drawn	RD	Checked	AP	Approved	EG
Project Code	NTA190002	Originator Code	NTA	QMS Code	S04.1				

Project Title	FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1						
Drawing Title	SITE CLEARANCE						
Drawing File Name	NTA190002-NTA-SPW SC-S04.1 XX 01-DR-KK-0003	Sheet Number	3 of 5	Status	E3	Rev	P04

SHEET 3 OF 5
MATCHLINE

APPROXIMATE LOCATION OF EXISTING
BUDDLEIA (BUTTERFLY BUSH) TO BE
REMOVED TO TIP OFF SITE. CONTRACTOR
IS TO ENSURE THE ENTIRE ROOT SYSTEM
IS REMOVED TO PREVENT RE-SPROUTING

RIVER DODDER

OLIVER PLUNKETT AVE.

LEGEND (CONTINUED):

- TAKE UP OR DOWN EXISTING
INSPECTION COVERS AND FRAME,
STOP COCK AND STOP / GAS VALVE/
FIRE HYDRANT AND SET ASIDE FOR
REUSE AT NEW PROPOSED LEVEL.
- EXISTING INSPECTION CHAMBER
COVER TO BE REMOVED TO
APPROVED LICENSED TIP OFF SITE.
- EXISTING INSPECTION CHAMBER
TO BE PROTECTED IN PLACE AND
ITS COVERS TO BE RAISED TO
PROPOSED LEVEL.
- EXISTING SIGN POST AND SIGN FACE
TO BE REMOVED TO APPROVED
LICENSED TIP OFF SITE. REFER TO
SIGN SCHEDULE FOR DETAILS.
- EXISTING SIGN POST TO BE REMOVED
TO APPROVED LICENSED TIP OFF SITE.
EXISTING SIGN FACE TO BE REMOVED
AND SET ASIDE FOR REUSE. REFER TO
SIGN SCHEDULE FOR DETAILS.
- EXISTING SIGN POST AND SIGN PLATE
TO BE REMOVED. AND SET ASIDE FOR
REUSE. REFER TO SIGN SCHEDULE
FOR DETAILS.
- REFUSE BIN TO BE REMOVED TO
STORE FOR RELOCATION
- TAKE UP OR DOWN EXISTING BOLLARD
PAVING SLAB AND FOUNDATION AND
REMOVE TO STORE
- EXISTING ROAD MARKINGS TO BE
REMOVED
- EXISTING MANHOLE TO BE
ADJUSTED TO SUIT NEW
FINISHED LEVEL AS REQUIRED
- EXISTING ROAD HUMP TO BE
REMOVED. REFER TO SERIES 0600
DRAWINGS FOR DETAILS.
- EXISTING VEGETATION TO BE
REMOVED TO TIP OFF SITE
- EXISTING HERITAGE FEATURE TO BE
PROTECTED IN PLACE
- EXISTING SIGNAL POLE TO BE
REMOVED TO STORE, SIGNAL HEADS,
DUCTING, AND CHAMBERS TO BE
REUSED ON SITE



AVAILABLE UTILITY
INFORMATION SUGGESTS
THE PRESENCE OF HIGH
VOLTAGE CABLES, GAS
MAINS AND OTHER UTILITY
SERVICES IN THE WORKS
AREA

FOR TENDER

NOTES:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
- EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
- ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
- DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY, THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
- ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
- CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
- WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
- THE LOCATION AND DEPTH OF SERVICES TO BE CHECKED ON SITE PRIOR TO COMMENCING ANY WORKS. NO WARRANTY GIVEN AS TO THE ACCURACY OF THE INFORMATION PROVIDED.
- LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS.
- THE CONTRACTOR IS TO ENSURE THAT DISTURBANCE TO LOCAL WATER, POWER OR COMMUNICATION SUPPLY MUST BE AVOIDED WHERE POSSIBLE, WHERE UNAVOIDABLE, IT MUST BE KEPT TO A MINIMUM AND PROPERTY OWNERS NOTIFIED.

LEGEND:

- TAKE UP OR DOWN EXISTING KERB, BEDDING, AND BACKING TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE
- TAKE UP OR DOWN EXISTING ANTIQUE GRANITE KERB, BEDDING AND BACKING TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE
- EXISTING CONCRETE PAVING SLABS
FOOTWAY, APPROX 600x600x63mm
CONCRETE PAVING SLAB, TO BE REMOVED TO STORE.
- EXISTING BLOCK PAVING FOOTWAY,
APPROX 22x180x80mm CONCRETE
BLOCK PAVIORS, AND APPROX
300x200mm RESTRAINING BEAMS TO BE REMOVED TO STORE.
- EXISTING FOOTPATH TO BE BROKEN
OUT AND EXCAVATED TO FORMATION
LEVEL MINIMUM OF 250mm CONCRETE
SURFACING AS PER 'NTA190002-NTA
-SCD_ZZ-S04.1_XX_01-DR-KK-0005'
- REFER TO SERIES 0700 DRAWINGS FOR
PAVEMENT TREATMENTS
- AREA OF VERGE TO BE EXCAVATED
AND STOCKPILED ON SITE FOR REUSE

TREE LEGEND:

- TREE STEM
NOMINAL ROOT
PROTECTION AREA (RPA)
ADJUSTED RPA

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040
Building Ireland's Future

NTA
Údarás Náisiúnta Iompair
National Transport Authority

Rev	Date	Dwn	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		Engineering Designer AECOM		
Date 28.04.2025	Scale 1:200@A1 1:400@A3	Drawn RD	Checked AP	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title SITE CLEARANCE			
Drawing File Name NTA190002-NTA-SPW_SC-S04.1_XX_01-DR-KK-0004	Sheet Number 4 of 5	Status E3	Rev P04

RIVER DODDER

LONDONBRIDGE ROAD


LONDON BRIDGE

LONDONBRIDGE ROAD

EXTENT OF WORKS

BATH AVENUE

TREE LEGEND:



Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titleblock. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish

Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drn	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client		Engineering Designer			
 Comhairle Cathrach Bhaile Átha Cliath Dublin City Council					
Date	28.04.2025	Scale	1:200@A1 1:400@A3	Drawn	RD
				Checked	AP
Project Code	NTA190002	Originator Code	NTA	QMS Code	S04.1
				Approved	EG

Project Title			
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title			
SITE CLEARANCE			
Drawing File Name		Sheet Number	Status
NTA190002-NTA-SPW_SC-S04.1_XX_01-DR-KK-0005		5 of 5	E3
		Rev	
		P04	

NOTES:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
- EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
- ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
- DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY, THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
- ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
- CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
- WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
- THE LOCATION AND DEPTH OF SERVICES TO BE CHECKED ON SITE PRIOR TO COMMENCING ANY WORKS. NO WARRANTY GIVEN AS TO THE ACCURACY OF THE INFORMATION PROVIDED.
- LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS.
- THE CONTRACTOR IS TO ENSURE THAT DISTURBANCE TO LOCAL WATER, POWER OR COMMUNICATION SUPPLY MUST BE AVOIDED WHERE POSSIBLE, WHERE UNAVOIDABLE, IT MUST BE KEPT TO A MINIMUM AND PROPERTY OWNERS NOTIFIED.


LEGEND:

- TAKE UP OR DOWN EXISTING KERB, BEDDING, AND BACKING TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE
- TAKE UP OR DOWN EXISTING ANTIQUE GRANITE KERB, BEDDING AND BACKING TO BE REMOVED TO APPROVED LICENSED TIP OFF SITE
- EXISTING CONCRETE PAVING SLABS FOOTWAY, APPROX 600x600x63mm CONCRETE PAVING SLAB, TO BE REMOVED TO STORE.
- EXISTING BLOCK PAVING FOOTWAY, APPROX 22x180x80mm CONCRETE BLOCK PAVIORS, AND APPROX 300x200mm RESTRAINING BEAMS TO BE REMOVED TO STORE.
- EXISTING FOOTPATH TO BE BROKEN OUT AND EXCAVATED TO FORMATION LEVEL MINIMUM OF 250mm CONCRETE SURFACING AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0005'
- REFER TO SERIES 0700 DRAWINGS FOR PAVEMENT TREATMENTS
- AREA OF VERGE TO BE EXCAVATED AND STOCKPILED ON SITE FOR REUSE



AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER



TREE LEGEND:

- TREE STEM
- NOMINAL ROOT PROTECTION AREA (RPA)
- ADJUSTED RPA

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
2. EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
3. ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
4. DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
5. ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
6. WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORK THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
7. ALL DRAINAGE WORKS TO COMPLY WITH THE GREATER DUBLIN REGIONAL CODE OF PRACTICE FOR DRAINAGE WORKS. THE USE OF PRECAST DRAINAGE INFRASTRUCTURE OR UPVC/ PLASTIC PIPEWORK WILL NOT BE PERMITTED.
8. GULLY GRATINGS AND FRAMES SHALL COMPLY WITH THE REQUIREMENTS OF ISEN 124 AND BE A MINIMUM CLASS D400.
9. IF TRAPPED GULLIES ARE INSTRUCTED TO BE USED BY THE EMPLOYER THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING.
10. ONLY HIPPO TYPE DUCTILE IRON TRAPPED GULLIES ARE TO BE USED. THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING. EXACT GULLY TYPE PROPOSED BY THE CONTRACTOR SHALL BE AGREED WITH THE EMPLOYERS REPRESENTATIVE PRIOR TO COMMENCEMENT OF ANY DRAINAGE WORKS.
11. THE CONTRACTOR IS TO CONDUCT A DRAINAGE SURVEY AT 2.0M CENTRES, ON STRAIGHT KERB SECTION AND 1.0M CENTRES ON RADI ADJACENT TO THE KERB LINE TO IDENTIFY ANY LOCAL LOW POINTS AND REGULATE THE ROAD SURFACE PRIOR TO LAYING THE FINISHED SURFACE TO ENSURE NO LOCAL LOW SPOTS RESULT IN SURFACE WATER PONDING.
12. EXISTING DRAINAGE NETWORK INFORMATION IS INDICATIVE ONLY AND IS BASED ON RECORD INFORMATION RECEIVED FROM DUBLIN CITY COUNCIL AND IRISH WATER. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM ALL DRAINAGE ON SITE PRIOR TO THE COMMENCEMENT OF ANY WORKS.
13. CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED. AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS' NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.

LEGEND:

- EXISTING GULLIES TO BE REPLACED WITH CYCLE FRIENDLY GULLIES TO INCLUDE CYCLE FREINDLY GULLY GRATES, MASTIC SURROUND, GULLY TAILS AND NON RETURN VALVES. REFER TO 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0002'
- PROPOSED INSPECTION CHAMBER COVER TO MATCH EXISTING CHAMBER COVER SPECIFICATION
- PROPOSED PRECAST DRAINAGE CHANNEL TO BE PROVIDED AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0003'
- EXISTING COMBINED SEWER
- EXISTING FOUL WATER SEWER
- EXISTING WATERMAIN
- PROPOSED POROUS ASPHALT CYCLE TRACK, REFER TO SERIES 1100 DRAWINGS
- PROPOSED FOOTPATH BUILDOUT

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER

Disclaimer

a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.


Building Ireland's Future

Údarás Náisiúnta Iompair
National Transport Authority

Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client		Engineering Designer		
 Comhairle Cathrach Bhaile Átha Cliath Dublin City Council				
Date 28.04.2025	Scale 1:200@A1 1:400@A3	Drawn RD	Checked AP	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title				
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1				
Drawing Title				
PROPOSED DRAINAGE				
Drawing File Name		Sheet Number	Status	Rev
NTA190002-NTA-DNR_RD-S04.1_XX_01-DR-KK-0001		1 of 5	E3	P04



1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
2. EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
3. ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
4. DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
5. ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
6. WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
7. ALL DRAINAGE WORKS TO COMPLY WITH THE GREATER DUBLIN REGIONAL CODE OF PRACTICE FOR DRAINAGE WORKS. THE USE OF PRECAST DRAINAGE INFRASTRUCTURE OR UPVC/ PLASTIC PIPEWORK WILL NOT BE PERMITTED.
8. GULLY GRATINGS AND FRAMES SHALL COMPLY WITH THE REQUIREMENTS OF IS/EN 124 AND BE A MINIMUM CLASS D400.
9. IF TRAPPED GULLIES ARE INSTRUCTED TO BE USED BY THE EMPLOYER THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING.
10. ONLY HIPPO TYPE DUCTILE IRON TRAPPED GULLIES ARE TO BE USED. THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING. EXACT GULLY TYPE PROPOSED BY THE CONTRACTOR SHALL BE AGREED WITH THE EMPLOYERS REPRESENTATIVE PRIOR TO COMMENCEMENT OF ANY DRAINAGE WORKS.
11. THE CONTRACTOR IS TO CONDUCT A DRAINAGE SURVEY AT 2.0M CENTRES, ON STRAIGHT KERB SECTION AND 1.0M CENTRES ON RADI ADJACENT TO THE KERB LINE TO IDENTIFY ANY LOCAL LOW POINTS AND REGULATE THE ROAD SURFACE PRIOR TO LAYING THE FINISHED SURFACE TO ENSURE NO LOCAL LOW SPOTS RESULT IN SURFACE WATER PONDING.
12. EXISTING DRAINAGE NETWORK INFORMATION IS INDICATIVE ONLY AND IS BASED ON RECORD INFORMATION RECEIVED FROM DUBLIN CITY COUNCIL AND IRISH WATER. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM ALL DRAINAGE ON SITE PRIOR TO THE COMMENCEMENT OF ANY WORKS.
13. CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED. AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS' NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.

LEGEND:

- EXISTING GULLIES TO BE REPLACED WITH CYCLE FRIENDLY GULLIES TO INCLUDE CYCLE FREINDLY GULLY GRATES, MASTIC SURROUND, GULLY TAILS AND NON RETURN VALVES. REFER TO 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0002'
- PROPOSED INSPECTION CHAMBER COVER TO MATCH EXISTING CHAMBER COVER SPECIFICATION
- PROPOSED PRECAST DRAINAGE CHANNEL TO BE PROVIDED AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0003'
- EXISTING COMBINED SEWER
- EXISTING FOUL WATER SEWER
- EXISTING WATERMAIN
- PROPOSED POROUS ASPHALT CYCLE TRACK, REFER TO SERIES 1100 DRAWINGS
- PROPOSED FOOTPATH BUILDOUT

TREE LEGEND:

- TREE STEM
- NOMINAL ROOT PROTECTION AREA (RPA)
- ADJUSTED RPA

Disclaimer

a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.


e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client		Engineering Designer			
 Comhairle Cathrach Bhaile Átha Cliath Dublin City Council					
Date	28.04.2025	Scale	1:200@A1 1:400@A3	Drawn	RD
				Checked	AP
				Approved	EG
Project Code	NTA190002	Originator Code	NTA	QMS Code	S04.1

Project Title			
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title			
PROPOSED DRAINAGE			
Drawing File Name	NTA190002-NTA-DNR_RD-S04.1_XX_01-DR-KK-0002	Sheet Number	2 of 5
Status	E3	Rev	P04



TREE LEGEND:

- TREE STEM
- NOMINAL ROOT PROTECTION AREA (RPA)
- ADJUSTED RPA

- NOTES:**
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - ALL DRAINAGE WORKS TO COMPLY WITH THE GREATER DUBLIN REGIONAL CODE OF PRACTICE FOR DRAINAGE WORKS. THE USE OF PRECAST DRAINAGE INFRASTRUCTURE OR UPVC/ PLASTIC PIPEWORK WILL NOT BE PERMITTED.
 - GULLY GRATINGS AND FRAMES SHALL COMPLY WITH THE REQUIREMENTS OF ISEN 124 AND BE A MINIMUM CLASS D400.
 - IF TRAPPED GULLIES ARE INSTRUCTED TO BE USED BY THE EMPLOYER THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING.
 - ONLY HIPPO TYPE DUCTILE IRON TRAPPED GULLIES ARE TO BE USED. THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING. EXACT GULLY TYPE PROPOSED BY THE CONTRACTOR SHALL BE AGREED WITH THE EMPLOYERS REPRESENTATIVE PRIOR TO COMMENCEMENT OF ANY DRAINAGE WORKS.
 - THE CONTRACTOR IS TO CONDUCT A DRAINAGE SURVEY AT 2.0M CENTRES, ON STRAIGHT KERB SECTION AND 1.0M CENTRES ON RADI ADJACENT TO THE KERB LINE TO IDENTIFY ANY LOCAL LOW POINTS AND REGULATE THE ROAD SURFACE PRIOR TO LAYING THE FINISHED SURFACE TO ENSURE NO LOCAL LOW SPOTS RESULT IN SURFACE WATER PONDING.
 - EXISTING DRAINAGE NETWORK INFORMATION IS INDICATIVE ONLY AND IS BASED ON RECORD INFORMATION RECEIVED FROM DUBLIN CITY COUNCIL AND IRISH WATER. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM ALL DRAINAGE ON SITE PRIOR TO THE COMMENCEMENT OF ANY WORKS.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED. TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS' NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.

LEGEND:

- EXISTING GULLIES TO BE REPLACED WITH CYCLE FRIENDLY GULLIES TO INCLUDE CYCLE FREINDLY GULLY GRATES, MASTIC SURROUND, GULLY TAILS AND NON RETURN VALVES. REFER TO 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0002'
- PROPOSED INSPECTION CHAMBER COVER TO MATCH EXISTING CHAMBER COVER SPECIFICATION
- PROPOSED PRECAST DRAINAGE CHANNEL TO BE PROVIDED AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0003'
- COMB EXISTING COMBINED SEWER
- FOUL EXISTING FOUL WATER SEWER
- WM EXISTING WATERMAIN
- PROPOSED POROUS ASPHALT CYCLE TRACK, REFER TO SERIES 1100 DRAWINGS
- PROPOSED FOOTPATH BUILDOUT

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Building Ireland's Future

Údarás Náisiúnta Iompair
National Transport Authority

Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client: Comhairle Cathrach
Bhaile Átha Cliath
Dublin City Council

Engineering Designer:

Date	28.04.2025	Scale	1:200@A1 1:400@A3	Drawn	RD	Checked	AP	Approved	EG
Project Code	NTA190002	Originator Code	NTA	QMS Code	S04.1				

Project Title	FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1
Drawing Title	PROPOSED DRAINAGE
Drawing File Name	NTA190002-NTA-DNR_RD-S04.1_XX_01-DR-KK-0003
Sheet Number	3 of 5
Status	E3
Rev	P04

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
2. EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
3. ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
4. DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
5. ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
6. WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
7. ALL DRAINAGE WORKS TO COMPLY WITH THE GREATER DUBLIN REGIONAL CODE OF PRACTICE FOR DRAINAGE WORKS. THE USE OF PRECAST DRAINAGE INFRASTRUCTURE OR UPVC/ PLASTIC PIPEWORK WILL NOT BE PERMITTED.
8. GULLY GRATINGS AND FRAMES SHALL COMPLY WITH THE REQUIREMENTS OF IS/EN 124 AND BE A MINIMUM CLASS D400.
9. IF TRAPPED GULLIES ARE INSTRUCTED TO BE USED BY THE EMPLOYER THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING.
10. ONLY HIPPO TYPE DUCTILE IRON TRAPPED GULLIES ARE TO BE USED. THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING. EXACT GULLY TYPE PROPOSED BY THE CONTRACTOR SHALL BE AGREED WITH THE EMPLOYERS REPRESENTATIVE PRIOR TO COMMENCEMENT OF ANY DRAINAGE WORKS.
11. THE CONTRACTOR IS TO CONDUCT A DRAINAGE SURVEY AT 2.0M CENTRES, ON STRAIGHT KERB SECTION AND 1.0M CENTRES ON RADI ADJACENT TO THE KERB LINE TO IDENTIFY ANY LOCAL LOW POINTS AND REGULATE THE ROAD SURFACE PRIOR TO LAYING THE FINISHED SURFACE TO ENSURE NO LOCAL LOW SPOTS RESULT IN SURFACE WATER PONDING.
12. EXISTING DRAINAGE NETWORK INFORMATION IS INDICATIVE ONLY AND IS BASED ON RECORD INFORMATION RECEIVED FROM DUBLIN CITY COUNCIL AND IRISH WATER. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM ALL DRAINAGE ON SITE PRIOR TO THE COMMENCEMENT OF ANY WORKS.
13. CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED. AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS' NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.

LEGEND:

- EXISTING GULLIES TO BE REPLACED WITH CYCLE FRIENDLY GULLIES TO INCLUDE CYCLE FREINDLY GULLY GRATES, MASTIC SURROUND, GULLY TAILS AND NON RETURN VALVES. REFER TO 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0002'
- PROPOSED INSPECTION CHAMBER COVER TO MATCH EXISTING CHAMBER COVER SPECIFICATION
- PROPOSED PRECAST DRAINAGE CHANNEL TO BE PROVIDED AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0003'
- EXISTING COMBINED SEWER
- EXISTING FOUL WATER SEWER
- EXISTING WATERMAIN
- PROPOSED POROUS ASPHALT CYCLE TRACK, REFER TO SERIES 1100 DRAWINGS
- PROPOSED FOOTPATH BUILDOUT

TREE LEGEND:

- TREE STEM
- NOMINAL ROOT PROTECTION AREA (RPA)
- ADJUSTED RPA

Disclaimer

a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.





Rev	Date	Drn	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client		Engineering Designer	
Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		AECOM	
Date	28.04.2025	Scale	1:200@A1 1:400@A3
Project Code	NTA190002	Originator Code	NTA
QMS Code		Drawn	RD
		Checked	AP
		Approved	EG

Project Title			
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title			
PROPOSED DRAINAGE			
Drawing File Name		Sheet Number	Status
NTA190002-NTA-DNR_RD-S04.1_XX_01-DR-KK-0004		4 of 5	E3
		Rev	P04

DO NOT SCALE USE FIGURED DIMENSIONS ONLY



- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
- EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
- ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
- DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
- ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
- WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
- ALL DRAINAGE WORKS TO COMPLY WITH THE GREATER DUBLIN REGIONAL CODE OF PRACTICE FOR DRAINAGE WORKS. THE USE OF PRECAST DRAINAGE INFRASTRUCTURE OR UPVC/ PLASTIC PIPEWORK WILL NOT BE PERMITTED.
- GULLY GRATINGS AND FRAMES SHALL COMPLY WITH THE REQUIREMENTS OF ISEN 124 AND BE A MINIMUM CLASS D400.
- IF TRAPPED GULLIES ARE INSTRUCTED TO BE USED BY THE EMPLOYER THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING.
- ONLY HIPPO TYPE DUCTILE IRON TRAPPED GULLIES ARE TO BE USED. THEY SHALL BE A COMPLETE INTEGRATED DUCTILE IRON WITH AN INTEGRAL TRAP AND HINGED CLEANING EYE COVER FOR RODDING. EXACT GULLY TYPE PROPOSED BY THE CONTRACTOR SHALL BE AGREED WITH THE EMPLOYERS REPRESENTATIVE PRIOR TO COMMENCEMENT OF ANY DRAINAGE WORKS.
- THE CONTRACTOR IS TO CONDUCT A DRAINAGE SURVEY AT 2.0M CENTRES, ON STRAIGHT KERB SECTION AND 1.0M CENTRES ON RADI ADJACENT TO THE KERB LINE TO IDENTIFY ANY LOCAL LOW POINTS AND REGULATE THE ROAD SURFACE PRIOR TO LAYING THE FINISHED SURFACE TO ENSURE NO LOCAL LOW SPOTS RESULT IN SURFACE WATER PONDING.
- EXISTING DRAINAGE NETWORK INFORMATION IS INDICATIVE ONLY AND IS BASED ON RECORD INFORMATION RECEIVED FROM DUBLIN CITY COUNCIL AND IRISH WATER. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM ALL DRAINAGE ON SITE PRIOR TO THE COMMENCEMENT OF ANY WORKS.
- CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED. TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS' NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.

LEGEND:

- EXISTING GULLIES TO BE REPLACED WITH CYCLE FRIENDLY GULLIES TO INCLUDE CYCLE FREINDLY GULLY GRATES, MASTIC SURROUND, GULLY TAILS AND NON RETURN VALVES. REFER TO 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0002'
- PROPOSED INSPECTION CHAMBER COVER TO MATCH EXISTING CHAMBER COVER SPECIFICATION
- PROPOSED PRECAST DRAINAGE CHANNEL TO BE PROVIDED AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0003'
- COMB - EXISTING COMBINED SEWER
- FOUL - EXISTING FOUL WATER SEWER
- WM - EXISTING WATERMAIN
- PROPOSED POROUS ASPHALT CYCLE TRACK, REFER TO SERIES 1100 DRAWINGS
- PROPOSED FOOTPATH BUILDOUT



AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish

Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners, and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this information. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.


e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client		Engineering Designer		
Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		AECOM		
Date 28.04.2025	Scale 1:200@A1 1:400@A3	Drawn RD	Checked AP	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title				
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1				
Drawing Title				
PROPOSED DRAINAGE				
Drawing File Name		Sheet Number	Status	Rev
NTA190002-NTA-DNR_RD-S04.1_XX_01-DR-KK-0005		5 of 5	E3	P04



TREE LEGEND:

- TREE STEM
- NOMINAL ROOT PROTECTION AREA (RPA)
- ADJUSTED RPA

LEGEND (CONTINUED):

- TOPSOILING OF 150mm, TOPSOIL CLASS 5A TO BE REMOVED FROM STOCKPILE ON SITE AND LAID
- PLANING OF 20mm FROM EXISTING CONCRETE SURFACING

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

- ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND
- NOTES:**
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS.
 - THE LOCATION AND DEPTH OF SERVICES TO BE CHECKED ON SITE PRIOR TO COMMENCING ANY WORKS. NO WARRANTY GIVEN AS TO THE ACCURACY OF THE INFORMATION PROVIDED.
 - THE EMPLOYER IS TO BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO COMMENCEMENT OF WORKS ON SITE
 - THE CONTRACTOR IS TO ENSURE THAT DISTURBANCE TO LOCAL WATER, POWER OR COMMUNICATION SUPPLY IS AVOIDED WHERE POSSIBLE, WHERE UNAVOIDABLE, IT MUST BE KEPT TO A MINIMUM AND PROPERTY OWNERS NOTIFIED.

- LEGEND:**
- EXISTING AREA TO BE EXCAVATED TO A MINIMUM OF 370mm TO SUITABLE FORMATION LEVEL
 - EXISTING AREA TO BE BROKEN OUT TO DEPTHS SUITABLE FOR DETAILS RM001 AND RM002, AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. REFER TO DRAWING 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0004'
 - EXISTING AREA TO BE BROKEN OUT TO DEPTHS SUITABLE FOR DETAIL RM012, AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. REFER TO DRAWING 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0004'
 - EXISTING CONCRETE SURFACE TO BE BROKEN OUT TO A DEPTH OF 70mm TO ALLOW FOR PROPOSED PAVEMENT TYPE B / RAMP REFER TO DRAWINGS 'NTA190002-NTA-PAV_PV-S04.1_XX_01-DR-KK-0001 TO 0005'
 - FOR PROPOSED PAVEMENT WORKS REFER TO SERIES 0700 DRAWINGS
 - EXISTING AREA TO BE EXCAVATED TO A SUITABLE DEPTH FOR FULL DEPTH CONSTRUCTION. REFER TO SERIES 0700 FOR MORE DETAIL
 - EXISTING AREA TO BE EXCAVATED TO A MINIMUM OF 210mm (60mm REDUCTION, 150mm TOPSOIL MIN REPLACED), ACCEPTABLE MATERIAL CLASS 5A TO BE STOCKPILED ON SITE.

FOR TENDER

© National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in meters and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station. The information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superseded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.										The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.									
Rev		Date		Drn		Chk'd		App'd		Description									
P01		22.09.2023		RD		AB		EG		ISSUED FOR TENDER REVIEW									
P02		21.12.2023		GH		AB		EG		ISSUED FOR TENDER REVIEW									
P03		12.01.2024		AK		AB		EG		ISSUED FOR TENDER									
P04		29.04.2025		RD		AP		EG		ISSUED FOR TENDER									

Project Ireland 2040
Building Ireland's Future

Údarás Náisiúnta Iompair
National Transport Authority

Date

29.04.2025

Scale

1:200@A1
1:400@A3

Drawn

RD

Checked

AP

Approved

EG

Project Code

NTA190002

Originator Code

NTA

QMS Code

S04.1

Drawing File Name

NTA190002-NTA-ERW_ER-S04.1_XX_01-DR-KK-0001

Sheet Number

1 of 5

Status

E3

Rev

P04

Fitzwilliam Point



RIVER DODDER

FITZWILLIAM QUAY

14-15

16-38

- NOTES:**
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS.
 - THE LOCATION AND DEPTH OF SERVICES TO BE CHECKED ON SITE PRIOR TO COMMENCING ANY WORKS. NO WARRANTY GIVEN AS TO THE ACCURACY OF THE INFORMATION PROVIDED.
 - THE EMPLOYER IS TO BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO COMMENCEMENT OF WORKS ON SITE
 - THE CONTRACTOR IS TO ENSURE THAT DISTURBANCE TO LOCAL WATER, POWER OR COMMUNICATION SUPPLY IS AVOIDED WHERE POSSIBLE, WHERE UNAVOIDABLE, IT MUST BE KEPT TO A MINIMUM AND PROPERTY OWNERS NOTIFIED.

- LEGEND:**
- EXISTING AREA TO BE EXCAVATED TO A MINIMUM OF 370mm TO SUITABLE FORMATION LEVEL
 - EXISTING AREA TO BE BROKEN OUT TO DEPTHS SUITABLE FOR DETAILS RM001 AND RM002, AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. REFER TO DRAWING 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0004'
 - EXISTING AREA TO BE BROKEN OUT TO DEPTHS SUITABLE FOR DETAIL RM012, AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. REFER TO DRAWING 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0004'
 - EXISTING CONCRETE SURFACE TO BE BROKEN OUT TO A DEPTH OF 70mm TO ALLOW FOR PROPOSED PAVEMENT TYPE B / RAMP REFER TO DRAWINGS 'NTA190002-NTA-PAV_PV-S04.1_XX_01-DR-KK-0001 TO 0005'
 - FOR PROPOSED PAVEMENT WORKS REFER TO SERIES 0700 DRAWINGS
 - EXISTING AREA TO BE EXCAVATED TO A SUITABLE DEPTH FOR FULL DEPTH CONSTRUCTION. REFER TO SERIES 0700 FOR MORE DETAIL
 - EXISTING AREA TO BE EXCAVATED TO A MINIMUM OF 210mm (60mm REDUCTION, 150mm TOPSOIL MIN REPLACED), ACCEPTABLE MATERIAL CLASS 5A TO BE STOCKPILED ON SITE.


FOR TENDER

- LEGEND (CONTINUED):**
- TOPSOILING OF 150mm, TOPSOIL CLASS 5A TO BE REMOVED FROM STOCKPILE ON SITE AND LAID
 - PLANING OF 20mm FROM EXISTING CONCRETE SURFACING



AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

TREE LEGEND:



Disclaimer

a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	29.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client		Engineering Designer							
 Comhairle Cathrach Bhaile Átha Cliath Dublin City Council									
Date	29.04.2025	Scale	1:200@A1 1:400@A3	Drawn	RD	Checked	AP	Approved	EG
Project Code		Originator Code		QMS Code					
NTA190002		NTA		S04.1					

Project Title			
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title			
EARTHWORKS			
Drawing File Name	NTA190002-NTA-ERW_ER-S04.1_XX_01-DR-KK-0002	Sheet Number	2 of 5
Status	E3	Rev	P04



- NOTES:**
1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 2. EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 3. ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 4. DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 5. ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 6. CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 7. WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 8. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS.
 9. THE LOCATION AND DEPTH OF SERVICES TO BE CHECKED ON SITE PRIOR TO COMMENCING ANY WORKS. NO WARRANTY GIVEN AS TO THE ACCURACY OF THE INFORMATION PROVIDED.
 10. THE EMPLOYER IS TO BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO COMMENCEMENT OF WORKS ON SITE
 11. THE CONTRACTOR IS TO ENSURE THAT DISTURBANCE TO LOCAL WATER, POWER OR COMMUNICATION SUPPLY IS AVOIDED WHERE POSSIBLE, WHERE UNAVOIDABLE, IT MUST BE KEPT TO A MINIMUM AND PROPERTY OWNERS NOTIFIED.

- LEGEND:**
- EXISTING AREA TO BE EXCAVATED TO A MINIMUM OF 370mm TO SUITABLE FORMATION LEVEL
 - EXISTING AREA TO BE BROKEN OUT TO DEPTHS SUITABLE FOR DETAILS RM001 AND RM002, AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. REFER TO DRAWING 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0004'
 - EXISTING AREA TO BE BROKEN OUT TO DEPTHS SUITABLE FOR DETAIL RM012, AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. REFER TO DRAWING 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0004'
 - EXISTING CONCRETE SURFACE TO BE BROKEN OUT TO A DEPTH OF 70mm TO ALLOW FOR PROPOSED PAVEMENT TYPE B / RAMP REFER TO DRAWINGS 'NTA190002-NTA-PAV_PV-S04.1_XX_01-DR-KK-0001 TO 0005'
 - FOR PROPOSED PAVEMENT WORKS REFER TO SERIES 0700 DRAWINGS
 - EXISTING AREA TO BE EXCAVATED TO A SUITABLE DEPTH FOR FULL DEPTH CONSTRUCTION. REFER TO SERIES 0700 FOR MORE DETAIL
 - EXISTING AREA TO BE EXCAVATED TO A MINIMUM OF 210mm (60mm REDUCTION, 150mm TOPSOIL MIN REPLACED), ACCEPTABLE MATERIAL CLASS 5A TO BE STOCKPILED ON SITE.

- LEGEND (CONTINUED):**
- TOPSOILING OF 150mm, TOPSOIL CLASS 5A TO BE REMOVED FROM STOCKPILE ON SITE AND LAID
 - PLANING OF 20mm FROM EXISTING CONCRETE SURFACING

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER

- TREE LEGEND:**
- TREE STEM
 - NOMINAL ROOT PROTECTION AREA (RPA)
 - ADJUSTED RPA

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Dwn	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	29.04.2025	RD	AP	EG	ISSUED FOR TENDER



AECOM

Date	29.04.2025	Scale	1:200@A1 1:400@A3	Drawn	RD	Checked	AP	Approved	EG
Project Code	NTA190002	Originator Code	NTA	QMS Code	S04.1				

Project Title	FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1
Drawing Title	EARTHWORKS
Drawing File Name	NTA190002-NTA-ERW_ER-S04.1_XX_01-DR-KK-0003
Sheet Number	3 of 5
Status	E3
Rev	P04

- NOTES:**
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS.
 - THE LOCATION AND DEPTH OF SERVICES TO BE CHECKED ON SITE PRIOR TO COMMENCING ANY WORKS. NO WARRANTY GIVEN AS TO THE ACCURACY OF THE INFORMATION PROVIDED.
 - THE EMPLOYER IS TO BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO COMMENCEMENT OF WORKS ON SITE
 - THE CONTRACTOR IS TO ENSURE THAT DISTURBANCE TO LOCAL WATER, POWER OR COMMUNICATION SUPPLY IS AVOIDED WHERE POSSIBLE, WHERE UNAVOIDABLE, IT MUST BE KEPT TO A MINIMUM AND PROPERTY OWNERS NOTIFIED.

- LEGEND:**
- EXISTING AREA TO BE EXCAVATED TO A MINIMUM OF 370mm TO SUITABLE FORMATION LEVEL
 - EXISTING AREA TO BE BROKEN OUT TO DEPTHS SUITABLE FOR DETAILS RM001 AND RM002, AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. REFER TO DRAWING 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0004'
 - EXISTING AREA TO BE BROKEN OUT TO DEPTHS SUITABLE FOR DETAIL RM012, AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. REFER TO DRAWING 'NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0004'
 - EXISTING CONCRETE SURFACE TO BE BROKEN OUT TO A DEPTH OF 70mm TO ALLOW FOR PROPOSED PAVEMENT TYPE B / RAMP REFER TO DRAWINGS 'NTA190002-NTA-PAV_PV-S04.1_XX_01-DR-KK-0001 TO 0005'
 - FOR PROPOSED PAVEMENT WORKS REFER TO SERIES 0700 DRAWINGS
 - EXISTING AREA TO BE EXCAVATED TO A SUITABLE DEPTH FOR FULL DEPTH CONSTRUCTION. REFER TO SERIES 0700 FOR MORE DETAIL
 - EXISTING AREA TO BE EXCAVATED TO A MINIMUM OF 210mm (60mm REDUCTION, 150mm TOPSOIL MIN REPLACED), ACCEPTABLE MATERIAL CLASS 5A TO BE STOCKPILED ON SITE.

- LEGEND (CONTINUED):**
- TOPSOILING OF 150mm, TOPSOIL CLASS 5A TO BE REMOVED FROM STOCKPILE ON SITE AND LAID
 - PLANING OF 20mm FROM EXISTING CONCRETE SURFACING



AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER

- TREE LEGEND:**
- TREE STEM
 - NOMINAL ROOT PROTECTION AREA (RPA)
 - ADJUSTED RPA

Disclaimer

a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titleblock. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.


e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	29.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		Engineering Designer AECOM		
Date 29.04.2025	Scale 1:200@A1 1:400@A3	Drawn RD	Checked AP	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title EARTHWORKS			
Drawing File Name NTA190002-NTA-ERW_ER-S04.1_XX_01-DR-KK-0005	Sheet Number 5 of 5	Status E3	Rev P04



- ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND
- NOTES:
1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS, ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 2. EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 3. ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 4. DO NOT SCALE FROM THIS DRAWING, ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 5. ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 6. CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED. AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 7. WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 8. EXISTING CARRIAGEWAY TO BE SAWCUT AND ADJOINED WITH PROPOSED KERBLINE.
 9. HOT APPLIED SEALANT TO CLAUSE 1017.2 AND 1017.3 TO BE APPLIED AT ROAD PAVEMENT/KERB/CHANNEL INTERFACE.
 10. WHERE POSSIBLE ROAD SURFACE PAVEMENT JOINTS TO BE LAID IN LOCATION OF PROPOSED LANE MARKINGS.
 11. BOND COAT TO BE APPLIED TO ALL SURFACES IN ACCORDANCE WITH CLAUSE 10.1.4 900 SERIES INCLUDING HBM LAYERS.
 12. FOR DEPTHS OF PAVEMENT EXCAVATION GREATER THEN 100MM THE CONTRACTOR IS TO UNDERTAKE A LOCALISED GPR SURVEY TO IDENTIFY UTILITIES. IF ANY UTILITY IS IDENTIFIED THAT MAY IMPACT THE PROPOSED WORKS THIS IS TO BE DISCUSSED WITH THE EMPLOYERS REPRESENTATIVE AND DUBLIN CITY COUNCIL BEFORE WORKS BEGIN. GPR SURVEY AND ASSOCIATED REPORT IS TO BE CIRCULATED TO DUBLIN CITY.
 13. ALL PLANED AREAS MUST BE RESURFACED TO FINISHED ROAD LEVEL ON THE SAME DAY. PLANED AREAS MUST UNDER NO CIRCUMSTANCES BE OPENED TO LIVE TRAFFIC.

- LEGEND:**
- TYPE A - FLEXIBLE PAVEMENT CONSTRUCTION WITH STONE MASTIC ASPHALT SYSTEM, PLANE 50mm, LAY 50mm OF SMA 10 SURF PMB 65/100-60 DES SURFACE COURSE
- TYPE B - CONCRETE SURFACE TO BE REINSTATED WITH ASPHALT TO EXISTING CARRIAGEWAY LEVEL. BREAK OUT 70mm, LAY 20mm OF SMA 6 BIN 70/100 REGULATING, BOND COAT, LAY GEOGRID, LAY 50mm SMA 10 SURF PMB 65/100-60 DES SURFACE COURSE
- TYPE C - RED ASPHALT SURFACING SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 20MM AND APPLY BOND COAT
- TYPE D - POROUS ASPHALT CYCLE TRACK. SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 30MM OVER, BINDER COURSE, AC20 40/60, DEPTH 60MM, 30mm 2/14mm CHOKER COURSE, 250mm 4/20mm CRUSHED CLEAN COARSE GRADED AGGREGATE, PER BS 7533-13, CONTRACTOR TO ALLOW FOR GEOTEXTILE AS PER APPENDIX 6/5
- TYPE E - FLEXIBLE PAVEMENT CONSTRUCTION WITH STONE RED MASTIC ASPHALT SYSTEM. SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 25MM OVER, BINDER COURSE, AC20 40/60, DEPTH 60MM, OVER DENSE BASE AC32 40/60, DEPTH 250MM OVER SUBBASE, GRANULAR MATERIAL TYPE 808 (TII UGM AC), DEPTH 300MM. AS PER RM013, CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
- PROPOSED SPEED RESTRICTION RAMP AS PER NTA190002-NTA-SCD_ZZ-S04.2_XX_00-DR-KK-0003'
- PROPOSED FOOTPATH BUILDOUT OVER EXISTING CARRIAGEWAY
- PROPOSED CYCLE RAMP

FOR TENDER

- TREE LEGEND:**
- TREE STEM
 - NOMINAL ROOT PROTECTION AREA (RPA)
 - ADJUSTED RPA

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Building Ireland's Future

Údarás Náisiúnta Iompair
National Transport Authority

Rev	Date	Dwn	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client

Engineering Designer

Date

28.04.2025

Scale

1:200@A1
1:400@A1

Drawn

RD

Checked

AP

Approved

EG

Project Code

NTA190002

Originator Code

NTA

QMS Code

S04.1

Project Title

FITZWILLIAM QUAY- LONDONBRIDGE STREET
SECTION 1

Drawing Title

PROPOSED PAVEMENTS WORKS

Drawing File Name

NTA190002-NTA-PAV_PV-S04.1_XX_01-DR-KK-0001

Sheet Number


1 of 5

Status

E3

Rev

P04



- ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND
- NOTES:
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS, ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING, ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED. AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - EXISTING CARRIAGEWAY TO BE SAWCUT AND ADJOINED WITH PROPOSED KERBLINE.
 - HOT APPLIED SEALANT TO CLAUSE 1017.2 AND 1017.3 TO BE APPLIED AT ROAD PAVEMENT/KERB/CHANNEL INTERFACE.
 - WHERE POSSIBLE ROAD SURFACE PAVEMENT JOINTS TO BE LAID IN LOCATION OF PROPOSED LANE MARKINGS.
 - BOND COAT TO BE APPLIED TO ALL SURFACES IN ACCORDANCE WITH CLAUSE 10.1.4 900 SERIES INCLUDING HBM LAYERS.
 - FOR DEPTHS OF PAVEMENT EXCAVATION GREATER THAN 100MM THE CONTRACTOR IS TO UNDERTAKE A LOCALISED GPR SURVEY TO IDENTIFY UTILITIES. IF ANY UTILITY IS IDENTIFIED THAT MAY IMPACT THE PROPOSED WORKS THIS IS TO BE DISCUSSED WITH THE EMPLOYERS REPRESENTATIVE AND DUBLIN CITY COUNCIL BEFORE WORKS BEGIN. GPR SURVEY AND ASSOCIATED REPORT IS TO BE CIRCULATED TO DUBLIN CITY.
 - ALL PLANED AREAS MUST BE RESURFACED TO FINISHED ROAD LEVEL ON THE SAME DAY. PLANED AREAS MUST UNDER NO CIRCUMSTANCES BE OPENED TO LIVE TRAFFIC.

- LEGEND:**
- TYPE A - FLEXIBLE PAVEMENT CONSTRUCTION WITH STONE MASTIC ASPHALT SYSTEM, PLANE 50mm, LAY 50mm OF SMA 10 SURF PMB 65/100-60 DES SURFACE COURSE
- TYPE B - CONCRETE SURFACE TO BE REINSTATED WITH ASPHALT TO EXISTING CARRIAGEWAY LEVEL. BREAK OUT 70mm, LAY 20mm OF SMA 6 BIN 70/100 REGULATING, BOND COAT, LAY GEOGRID, LAY 50mm SMA 10 SURF PMB 65/100-60 DES SURFACE COURSE
- TYPE C - RED ASPHALT SURFACING SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 20MM AND APPLY BOND COAT
- TYPE D - POROUS ASPHALT CYCLE TRACK. SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 30MM OVER, BINDER COURSE, AC20 40/60, DEPTH 60MM, 30mm 2/14mm CHOKER COURSE, 250mm 4/20mm CRUSHED CLEAN COARSE GRADED AGGREGATE, PER BS 7533-13, CONTRACTOR TO ALLOW FOR GEOTEXTILE AS PER APPENDIX 6/5
- TYPE E - FLEXIBLE PAVEMENT CONSTRUCTION WITH STONE RED MASTIC ASPHALT SYSTEM. SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 25MM OVER, BINDER COURSE, AC20 40/60, DEPTH 60MM, OVER DENSE BASE AC32 40/60, DEPTH 250MM OVER SUBBASE, GRANULAR MATERIAL TYPE 808 (TII UGM AC), DEPTH 300MM. AS PER RM013, CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
- PROPOSED SPEED RESTRICTION RAMP AS PER NTA190002-NTA-SCD_ZZ-S04.2_XX_00-DR-KK-0003'
- PROPOSED FOOTPATH BUILDOUT OVER EXISTING CARRIAGEWAY
- PROPOSED CYCLE RAMP

- TREE LEGEND:**
- TREE STEM
 - NOMINAL ROOT PROTECTION AREA (RPA)
 - ADJUSTED RPA

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titleblock. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish


Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		Engineering Designer AECOM		
Date 28.04.2025	Scale 1:200@A1 1:400@A1	Drawn RD	Checked AP	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title PROPOSED PAVEMENTS WORKS			
Drawing File Name NTA190002-NTA-PAV_PV-S04.1_XX_01-DR-KK-0002	Sheet Number 2 of 5	Status E3	Rev P04



- ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND
- NOTES:
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS, ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING, ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - EXISTING CARRIAGEWAY TO BE SAWCUT AND ADJOINED WITH PROPOSED KERBLINE.
 - HOT APPLIED SEALANT TO CLAUSE 1017.2 AND 1017.3 TO BE APPLIED AT ROAD PAVEMENT/KERB/CHANNEL INTERFACE.
 - WHERE POSSIBLE ROAD SURFACE PAVEMENT JOINTS TO BE LAID IN LOCATION OF PROPOSED LANE MARKINGS.
 - BOND COAT TO BE APPLIED TO ALL SURFACES IN ACCORDANCE WITH CLAUSE 10.1.4 900 SERIES INCLUDING HBM LAYERS.
 - FOR DEPTHS OF PAVEMENT EXCAVATION GREATER THEN 100MM THE CONTRACTOR IS TO UNDERTAKE A LOCALISED GPR SURVEY TO IDENTIFY UTILITIES. IF ANY UTILITY IS IDENTIFIED THAT MAY IMPACT THE PROPOSED WORKS THIS IS TO BE DISCUSSED WITH THE EMPLOYERS REPRESENTATIVE AND DUBLIN CITY COUNCIL BEFORE WORKS BEGIN. GPR SURVEY AND ASSOCIATED REPORT IS TO BE CIRCULATED TO DUBLIN CITY.
 - ALL PLANED AREAS MUST BE RESURFACED TO FINISHED ROAD LEVEL ON THE SAME DAY. PLANED AREAS MUST UNDER NO CIRCUMSTANCES BE OPENED TO LIVE TRAFFIC.

- LEGEND:
- TYPE A - FLEXIBLE PAVEMENT CONSTRUCTION WITH STONE MASTIC ASPHALT SYSTEM, PLANE 50mm, LAY 50mm OF SMA 10 SURF PMB 65/100-60 DES SURFACE COURSE
- TYPE B - CONCRETE SURFACE TO BE REINSTATED WITH ASPHALT TO EXISTING CARRIAGEWAY LEVEL. BREAK OUT 70mm, LAY 20mm OF SMA 6 BIN 70/100 REGULATING, BOND COAT, LAY GEOGRID, LAY 50mm SMA 10 SURF PMB 65/100-60 DES SURFACE COURSE
- TYPE C - RED ASPHALT SURFACING SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 20MM AND APPLY BOND COAT
- TYPE D - POROUS ASPHALT CYCLE TRACK, SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 30MM OVER, BINDER COURSE, AC20 40/60, DEPTH 60MM, 30mm 2/14mm CHOKER COURSE, 250mm 4/20mm CRUSHED CLEAN COARSE GRADED AGGREGATE, PER BS 7533-13, CONTRACTOR TO ALLOW FOR GEOTEXTILE AS PER APPENDIX 6/5
- TYPE E - FLEXIBLE PAVEMENT CONSTRUCTION WITH STONE RED MASTIC ASPHALT SYSTEM. SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 25MM OVER, BINDER COURSE, AC20 40/60, DEPTH 60MM, OVER DENSE BASE AC32 40/60, DEPTH 250MM OVER SUBBASE, GRANULAR MATERIAL TYPE 808 (TII UGM AC), DEPTH 300MM. AS PER RM013, CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
- PROPOSED SPEED RESTRICTION RAMP AS PER NTA190002-NTA-SCD_ZZ-S04.2_XX_00-DR-KK-0003'
- PROPOSED FOOTPATH BUILDOUT OVER EXISTING CARRIAGEWAY
- PROPOSED CYCLE RAMP

- TREE LEGEND:
- TREE STEM
 - NOMINAL ROOT PROTECTION AREA (RPA)
 - ADJUSTED RPA

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners, and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drn	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		Engineering Designer AECOM		
Date 28.04.2025	Scale 1:200@A1 1:400@A1	Drawn RD	Checked AP	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title PROPOSED PAVEMENTS WORKS			
Drawing File Name NTA190002-NTA-PAV_PV-S04.1_XX_01-DR-KK-0003	Sheet Number 3 of 5	Status E3	Rev P04

MATCHLINE
SHEET 4 OF 5

ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588

NOTES:
THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER
RELEVANT ENGINEERING DRAWINGS, ANY DISCREPANCIES,
ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF
THE EMPLOYER.

EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.

ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.

DO NOT SCALE FROM THIS DRAWING, ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY, THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.

ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.

CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.

WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.

EXISTING CARRIAGEWAY TO BE SAWCUT AND ADJOINED WITH
PROPOSED KERBLINE.

HOT APPLIED SEALANT TO CLAUSE 1017.2 AND 1017.3 TO BE APPLIED AT ROAD PAVEMENT/KERB/CHANNEL INTERFACE.

WHERE POSSIBLE ROAD SURFACE PAVEMENT JOINTS TO BE LAID
IN LOCATION OF PROPOSED LANE MARKINGS.

BOND COAT TO BE APPLIED TO ALL SURFACES IN ACCORDANCE WITH CLAUSE 10.1.4 900 SERIES INCLUDING HBM LAYERS.

FOR DEPTHS OF PAVEMENT EXCAVATION GREATER THEN 100MM
THE CONTRACTOR IS TO UNDERTAKE A LOCALISED GPR SURVEY

IMPACT THE PROPOSED WORKS THIS IS TO BE DISCUSSED WITH THE EMPLOYERS REPRESENTATIVE AND DUBLIN CITY COUNCIL BEFORE WORKS BEGIN. GPR SURVEY AND ASSOCIATED REPORT IS TO BE CIRCULATED TO DUBLIN CITY.

ALL PLANED AREAS MUST BE RESURFACED TO FINISHED ROAD LEVEL ON THE SAME DAY. PLANED AREAS MUST UNDER NO CIRCUMSTANCES BE OPENED TO LIVE TRAFFIC.

LEGEND:

TYPE A - FLEXIBLE PAVEMENT
CONSTRUCTION WITH STONE MASTIC
ASPHALT SYSTEM. PLANE 50mm, LAY
50mm OF SMA 10 SURF PMB 65/100-60
DES SURFACE COURSE

TYPE B - CONCRETE SURFACE TO BE REINSTATED WITH ASPHALT TO EXISTING CARRIAGEWAY LEVEL. BREAK OUT 70mm, LAY 20mm OF SMA 6 BIN 70/100 REGULATING, BOND COAT, LAY GEOGRID, LAY 50mm SMA 10 SURF PMB 65/100-60 DES SURFACE COURSE

 TYPE C - RED ASPHALT SURFACING
SMA 6 SURF PMB 65/100-60 DES
SURFACE COURSE, DEPTH 20MM AND
APPLY BOND COAT

TYPE D - POROUS ASPHALT CYCLE
TRACK. SMA 6 SURF PMB 65/100-60 DES
SURFACE COURSE, DEPTH 30MM OVER,
BINDER COURSE, AC20 40/60, DEPTH
60MM, 30mm 2/14mm CHOKER COURSE,
250mm 4/20mm CRUSHED CLEAN
COARSE GRADED AGGREGATE, PER BS
7533-13, CONTRACTOR TO ALLOW FOR
GEOTEXTILE AS PER APPENDIX 6/5


TYPE E - FLEXIBLE PAVEMENT
CONSTRUCTION WITH STONE RED
MASTIC ASPHALT SYSTEM, SMA 6
SURF PMB 65/100-60 DES SURFACE
COURSE, DEPTH 25MM OVER, BINDER
COURSE, AC20 40/60, DEPTH 60MM,
OVER DENSE BASE AC32 40/60, DEPTH
250MM OVER SUBBASE, GRANULAR
MATERIAL TYPE 808 (TII UGM AC),
DEPTH 300MM. AS PER RM013,
CONSTRUCTION STANDARDS FOR
ROAD AND STREET WORKS IN DUBLIN
CITY COUNCIL.

PROPOSED SPEED RESTRICTION
RAMP AS PER NTA190002-NTA-SCD_
ZZ-S04.2_XX_00-DR-KK-0003'

 PROPOSED FOOTPATH BUILDOUT
OVER EXISTING CARRIAGEWAY PROPOSED CYCLE RAMP

FOR TENDER

TREE LEGEND:



Disclaimer

a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all relevant design drawings.

c. O.S. data used for plans is printed under Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish

Transverse Mercator Grid (ITM) as defined by OSI active ion GPS station.

Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should not be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or of any kind as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.




Rev	Date	Drn	Chk'd	App'd	Description
P01	22.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER

Client  Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		Engineering Designer 			
Date 28.04.2025	Scale 1:200@A1 1:400@A1	Drawn RD	Checked AP	Approved EG	
Project Code NTA190002	Originator Code NTA	QMS Code S04.1			

Project Title					FITZWILLIAM QUAY - LONDONBRIDGE STREET SECTION 1					
Drawing Title										
PROPOSED PAVEMENTS WORKS										
Drawing File Name					Sheet Number		Status		Rev	
NTA190002-NTA-PAV_PV-S04.1_XX_01-DR-KK-0004					4 of 5		E3		P04	

DO NOT SCALE USE FIGURED DIMENSIONS ONLY



GENERAL NOTE:
GRANITE KERBS REMOVED IN CLEARANCE WORKS ARE TO BE REUSED ON SITE IN AGREEMENT WITH THE EMPLOYERS REPRESENTATIVE.
PAVING SLABS, PAVIOURS, SETTS, AND BLOCKS REMOVED IN CLEARANCE WORKS ARE TO BE REUSED ON SITE IN AGREEMENT WITH THE EMPLOYERS REPRESENTATIVE.

- NOTES:**
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - ALL DIMENSIONS TO BE CHECKED BY THE CONTRACTOR ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - EXISTING CARRIAGEWAY TO BE SAWCUT AND ADJOINED WITH PROPOSED KERBLINE.
 - HOT APPLIED SEALANT TO CLAUSE 1017.2 AND 1017.3 TO BE APPLIED AT ROAD PAVEMENT/KERB/CHANNEL INTERFACE.
 - PRIOR TO ANY WORKS ON HISTORIC PAVERS OR KERBS CATALOGUING AND TRAINING IS TO BE CARRIED OUT BY THE CONTRACTOR AS DIRECTED BY THE EMPLOYERS REPRESENTATIVE IN ACCORDANCE WITH THE WORKS REQUIREMENTS.

- LEGEND:**
- PROPOSED EXTRUDED CONCRETE SEGREGATION KERB
 - PROPOSED IN-SITU CONCRETE KERB
 - PROPOSED IN-SITU CONCRETE DROPPED TRANSITION KERB
 - PROPOSED EDGING KERB AS PER
 - PROPOSED EXTRUDED 30 DEGREE SPLAY KERB WITH 60mm UPSTAND
 - PROPOSED GRANITE KERBS. INTEGRATION OF NEW KERBS TO BE AGREED WITH DCC ON SITE.
 - PROPOSED GRANITE DROP KERB. INTEGRATION OF NEW GRANITE DROP KERBS TO BE AFREED WITH DCC ON SITE.
 - CYCLE RAMP MINIMUM 25mm OF 10mm DWC LAID ON 50mm OF 20mm DBM BS4987
 - CYCLE RAMP TO BE FORMED WITHIN POROUS ASPHALT CYCLE TRACK
 - PROPOSED PRECAST DRAINAGE CHANNEL TO BE PROVIDED AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0003'
 - PROPOSED TYPE A BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'
 - PROPOSED TYPE B BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'
 - PROPOSED TYPE C BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'

LEGEND CONTINUED:

- POROUS ASPHALT CYCLE TRACK, SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 30MM OVER, BINDER COURSE, AC20/40/60, DEPTH 60MM, 30mm 2/14mm CHOKER COURSE, 250mm 4/20mm CRUSHED CLEAN COARSE GRADED AGGREGATE, PER BS 7533-13, CONTRACTOR TO ALLOW FOR GEOTEXTILE AS PER APPENDIX 6/5
- DEPOSITION OF 150mm CLASS 5A TOPSOIL AND GRASS SEEDING
- PROPOSED IN SITU CONCRETE FOOTWAY / TRAFFIC ISLAND AND IN SITU CONCRETE KERB AND ISLAND / FOOTPATH TO BE CAST AS ONE. IN SITU CONCRETE SURFACE CLASS XF4 APPROX 100mm DEPTH. IN SITU CONCRETE KERB APPROX DEPTH 300mm, WIDTH 200mm, SUBBASE NRA SRW CLAUSE 808 (TII UGM AC) MATERIAL APPROX 150mm DEPTH AS PER, RM001 AND RM002 OF THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL


- PROPOSED CONCRETE PAVING SLAB FOOTWAY APPROX 600X600X63mm CONCRETE PAVING SLAB, AND 3:1 SEMI-DRY SAND:CEMENT APPROX 30-50mm THICK AND APPROX. 100mm DEPTH, SUBBASE CEMENT BOUND MATERIAL CATEGORY 3 TO NRA SRW CLAUSE 1038, AS PER RM012 FOOTWAY DETAILS: CONCRETE PAVING SLABS, CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL
- PROPOSED TACTILE PAVING, RED OR BUFF COLOURED AS INDICATED ON DRAWINGS, LAID ON APPROX. 30mm TO 70mm FIBRE REINFORCED SEMI-DRY CONCRETE, MINIMUM BEDDING COMPRESSIVE STRENGTH 35N/mm², ON 150mm CLAUSE 808 (TII UGM AC), SURFACES SLOPING AT 10° OR LESS TO THE HORIZONTAL AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL IN ACCORDANCE WITH UK DOT GUIDANCE ON THE USE OF TACTILE PAVING SURFACES

TREE LEGEND:

- TREE STEM
- NOMINAL ROOT PROTECTION AREA (RPA)
- ADJUSTED RPA

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER

a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA. b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings. c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station. d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superseded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed. e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.					 Project Ireland 2040 Building Ireland's Future  Údarás Náisiúnta Iompair National Transport Authority		<table><tr><th>Rev</th><th>Date</th><th>Drm</th><th>Chk'd</th><th>App'd</th><th>Description</th></tr><tr><td>P01</td><td>21.09.2023</td><td>RD</td><td>AB</td><td>EG</td><td>ISSUED FOR TENDER REVIEW</td></tr><tr><td>P02</td><td>21.12.2023</td><td>GH</td><td>AB</td><td>EG</td><td>ISSUED FOR TENDER REVIEW</td></tr><tr><td>P03</td><td>12.01.2024</td><td>AK</td><td>AB</td><td>EG</td><td>ISSUED FOR TENDER</td></tr><tr><td>P04</td><td>28.04.2025</td><td>RD</td><td>AP</td><td>EG</td><td>ISSUED FOR TENDER</td></tr></table>	Rev	Date	Drm	Chk'd	App'd	Description	P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW	P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW	P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER	P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER	 Comhairle Cathrach Bhaile Átha Cliath Dublin City Council  AECOM <table><tr><th>Date</th><td>28.04.2025</td><th>Scale</th><td>1:200@A1 1:400@A3</td><th>Drawn</th><td>RD</td><th>Checked</th><td>AP</td><th>Approved</th><td>EG</td></tr><tr><th>Project Code</th><td>NTA190002</td><th>Originator Code</th><td>NTA</td><th>QMS Code</th><td colspan="4">S04.1</td><td></td></tr></table>	Date	28.04.2025	Scale	1:200@A1 1:400@A3	Drawn	RD	Checked	AP	Approved	EG	Project Code	NTA190002	Originator Code	NTA	QMS Code	S04.1					<table><tr><th colspan="2">Project Title</th><th colspan="2">Drawing Title</th><th colspan="2">Drawing File Name</th><th>Sheet Number</th><th>Status</th><th>Rev</th></tr><tr><td colspan="2">FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1</td><td colspan="2">PROPOSED KERBS, FOOTWAYS AND PAVED AREAS</td><td colspan="2">NTA190002-NTA-PAV_HS-S04.1_XX_01-DR-KK-0001</td><td>1 of 5</td><td>E3</td><td>P04</td></tr></table>	Project Title		Drawing Title		Drawing File Name		Sheet Number	Status	Rev	FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1		PROPOSED KERBS, FOOTWAYS AND PAVED AREAS		NTA190002-NTA-PAV_HS-S04.1_XX_01-DR-KK-0001		1 of 5	E3	P04
Rev	Date	Drm	Chk'd	App'd	Description																																																																								
P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW																																																																								
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW																																																																								
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER																																																																								
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER																																																																								
Date	28.04.2025	Scale	1:200@A1 1:400@A3	Drawn	RD	Checked	AP	Approved	EG																																																																				
Project Code	NTA190002	Originator Code	NTA	QMS Code	S04.1																																																																								
Project Title		Drawing Title		Drawing File Name		Sheet Number	Status	Rev																																																																					
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1		PROPOSED KERBS, FOOTWAYS AND PAVED AREAS		NTA190002-NTA-PAV_HS-S04.1_XX_01-DR-KK-0001		1 of 5	E3	P04																																																																					

Fitzwilliam Point



RIVER DODDER

FITZWILLIAM QUAY

CH-100

CH-150

14-15

16-38

LEGEND CONTINUED:

 POROUS ASPHALT CYCLE TRACK, SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 30MM OVER, BINDER COURSE, AC20/40/60, DEPTH 60MM, 30mm 2/14mm CHOKER COURSE, 250mm 4/20mm CRUSHED CLEAN COARSE GRADED AGGREGATE, PER BS 7533-13, CONTRACTOR TO ALLOW FOR GEOTEXTILE AS PER APPENDIX 6/5


 DEPOSITION OF 150mm CLASS 5A TOPSOIL AND GRASS SEEDING

 PROPOSED IN SITU CONCRETE FOOTWAY / TRAFFIC ISLAND AND IN SITU CONCRETE KERB AND ISLAND / FOOTPATH TO BE CAST AS ONE. IN SITU CONCRETE SURFACE CLASS XF4 APPROX 100mm DEPTH, IN SITU CONCRETE KERB APPROX DEPTH 300mm, WIDTH 200mm, SUBBASE NRA SRW CLAUSE 808 (TII UGM AC) MATERIAL APPROX 150mm DEPTH AS PER, RM001 AND RM002 OF THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL

 PROPOSED CONCRETE PAVING SLAB FOOTWAY APPROX 600X600X63mm CONCRETE PAVING SLAB, AND 3:1 SEMI-DRY SAND:CEMENT APPROX 30-50mm THICK AND APPROX. 100mm DEPTH, SUBBASE CEMENT BOUND MATERIAL CATEGORY 3 TO NRA SRW CLAUSE 1038, AS PER RM012 FOOTWAY DETAILS: CONCRETE PAVING SLABS, CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL

 PROPOSED TACTILE PAVING, RED OR BUFF COLOURED AS INDICATED ON DRAWINGS, LAID ON APPROX. 30mm TO 70mm FIBRE REINFORCED SEMI-DRY CONCRETE, MINIMUM BEDDING COMPRESSIVE STRENGTH 35N/mm2, ON 150mm CLAUSE 808 (TII UGM AC), SURFACES SLOPING AT 10° OR LESS TO THE HORIZONTAL AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL IN ACCORDANCE WITH UK DOT GUIDANCE ON THE USE OF TACTILE PAVING SURFACES

TREE LEGEND:

 TREE STEM
NOMINAL ROOT PROTECTION AREA (RPA)
ADJUSTED RPA



AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA


FOR TENDER

ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND

NOTES:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
- EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
- ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
- DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
- ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
- CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
- WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
- ALL DIMENSIONS TO BE CHECKED BY THE CONTRACTOR ON SITE PRIOR TO COMMENCEMENT OF WORKS.
- EXISTING CARRIAGEWAY TO BE SAWCUT AND ADJOINED WITH PROPOSED KERBLINE.
- HOT APPLIED SEALANT TO CLAUSE 1017.2 AND 1017.3 TO BE APPLIED AT ROAD PAVEMENT/KERB/CHANNEL INTERFACE.
- PRIOR TO ANY WORKS ON HISTORIC PAVERS OR KERBS CATALOGUING AND TRAINING IS TO BE CARRIED OUT BY THE CONTRACTOR AS DIRECTED BY THE EMPLOYERS REPRESENTATIVE IN ACCORDANCE WITH THE WORKS REQUIREMENTS.

LEGEND:

-  PROPOSED EXTRUDED CONCRETE SEGREGATION KERB
-  PROPOSED IN-SITU CONCRETE KERB
-  PROPOSED IN-SITU CONCRETE DROPPED TRANSITION KERB
-  PROPOSED EDGING KERB AS PER
-  PROPOSED EXTRUDED 30 DEGREE SPLAY KERB WITH 60mm UPSTAND
-  PROPOSED GRANITE KERB, INTEGRATION OF NEW KERBS TO BE AGREED WITH DCC ON SITE.

 PROPOSED GRANITE DROP KERB, INTEGRATION OF NEW GRANITE DROP KERBS TO BE AFREED WITH DCC ON SITE.

 CYCLE RAMP MINIMUM 25mm OF 10mm DWC LAID ON 50mm OF 20mm DBM BS4987

 CYCLE RAMP TO BE FORMED WITHIN POROUS ASPHALT CYCLE TRACK

 PROPOSED PRECAST DRAINAGE CHANNEL TO BE PROVIDED AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0003'

 PROPOSED TYPE A BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'

 PROPOSED TYPE B BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'

 PROPOSED TYPE C BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'

GENERAL NOTE:
GRANITE KERBS REMOVED IN CLEARANCE WORKS ARE TO BE REUSED ON SITE IN AGREEMENT WITH THE EMPLOYERS REPRESENTATIVE.
PAVING SLABS, PAVIOURS, SETTS, AND BLOCKS REMOVED IN CLEARANCE WORKS ARE TO BE REUSED ON SITE IN AGREEMENT WITH THE EMPLOYERS REPRESENTATIVE.


Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER

Client  Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		Engineering Designer AECOM		
Date 12.01.2024	Scale 1:200@A1 1:400@A3	Drawn AK	Checked AB	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1		Drawing Title PROPOSED KERBS, FOOTWAYS AND PAVED AREAS		
Drawing File Name NTA190002-NTA-PAV_HS-S04.1_XX_01-DR-KK-0002	Sheet Number 2 of 5	Status E3	Rev P03	



LEGEND CONTINUED:

- POROUS ASPHALT CYCLE TRACK, SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 30MM OVER, BINDER COURSE, AC20 40/60, DEPTH 60MM, 30mm 2/14mm CHOKER COURSE, 250mm 4/20mm CRUSHED CLEAN COARSE GRADED AGGREGATE, PER BS 7533-13, CONTRACTOR TO ALLOW FOR GEOTEXTILE AS PER APPENDIX 6/5
- DEPOSITION OF 150mm CLASS 5A TOPSOIL AND GRASS SEEDING
- PROPOSED IN SITU CONCRETE FOOTWAY / TRAFFIC ISLAND AND IN SITU CONCRETE KERB AND ISLAND / FOOTPATH TO BE CAST AS ONE. IN SITU CONCRETE SURFACE CLASS XF4 APPROX 100mm DEPTH, IN SITU CONCRETE KERB APPROX DEPTH 300mm, WIDTH 200mm, SUBBASE NRA SRW CLAUSE 808 (TII UGM AC) MATERIAL APPROX 150mm DEPTH AS PER, RM001 AND RM002 OF THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL
- PROPOSED CONCRETE PAVING SLAB FOOTWAY APPROX 600X800X63mm CONCRETE PAVING SLAB, AND 3:1 SEMI-DRY SAND:CEMENT APPROX 30-50mm THICK AND APPROX. 100mm DEPTH, SUBBASE CEMENT BOUND MATERIAL CATEGORY 3 TO NRA SRW CLAUSE 1038, AS PER RM012 FOOTWAY DETAILS: CONCRETE PAVING SLABS, CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL
- PROPOSED TACTILE PAVING, RED OR BUFF COLOURED AS INDICATED ON DRAWINGS, LAID ON APPROX. 30mm TO 70mm FIBRE REINFORCED SEMI-DRY CONCRETE, MINIMUM BEDDING COMPRESSIVE STRENGTH 35N/mm², ON 150mm CLAUSE 808 (TII UGM AC), SURFACES SLOPING AT 1° OR LESS TO THE HORIZONTAL AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL IN ACCORDANCE WITH UK DOT GUIDANCE ON THE USE OF TACTILE PAVING SURFACES

TREE LEGEND:

- TREE STEM
- NOMINAL ROOT PROTECTION AREA (RPA)
- ADJUSTED RPA

NOTES:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
- EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
- ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
- DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
- ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
- CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
- WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
- ALL DIMENSIONS TO BE CHECKED BY THE CONTRACTOR ON SITE PRIOR TO COMMENCEMENT OF WORKS.
- EXISTING CARRIAGEWAY TO BE SAWCUT AND ADJOINED WITH PROPOSED KERBLINE.
- HOT APPLIED SEALANT TO CLAUSE 1017.2 AND 1017.3 TO BE APPLIED AT ROAD PAVEMENT/KERB/CHANNEL INTERFACE.
- PRIOR TO ANY WORKS ON HISTORIC PAVERS OR KERBS CATALOGUING AND TRAINING IS TO BE CARRIED OUT BY THE CONTRACTOR AS DIRECTED BY THE EMPLOYERS REPRESENTATIVE IN ACCORDANCE WITH THE WORKS REQUIREMENTS.

LEGEND:

- PROPOSED EXTRUDED CONCRETE SEGREGATION KERB
- PROPOSED IN-SITU CONCRETE KERB
- PROPOSED IN-SITU CONCRETE DROPPED TRANSITION KERB
- PROPOSED EDGING KERB AS PER
- PROPOSED EXTRUDED 30 DEGREE SPLAY KERB WITH 60mm UPSTAND
- PROPOSED GRANITE KERB, INTEGRATION OF NEW KERBS TO BE AGREED WITH DCC ON SITE.
- PROPOSED GRANITE DROP KERB, INTEGRATION OF NEW GRANITE DROP KERBS TO BE AFREED WITH DCC ON SITE.
- CYCLE RAMP MINIMUM 25mm OF 10mm DWL LAID ON 50mm OF 20mm DBM BS4987
- CYCLE RAMP TO BE FORMED WITHIN POROUS ASPHALT CYCLE TRACK
- PROPOSED PRECAST DRAINAGE CHANNEL TO BE PROVIDED AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0003'
- PROPOSED TYPE A BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'
- PROPOSED TYPE B BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'
- PROPOSED TYPE C BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'

FOR TENDER

GENERAL NOTE:
GRANITE KERBS REMOVED IN CLEARANCE WORKS ARE TO BE REUSED ON SITE IN AGREEMENT WITH THE EMPLOYERS REPRESENTATIVE.
PAVING SLABS, PAVIOURS, SETTS, AND BLOCKS REMOVED IN CLEARANCE WORKS ARE TO BE REUSED ON SITE IN AGREEMENT WITH THE EMPLOYERS REPRESENTATIVE.


Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken as appropriate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER

Client Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		Engineering Designer AECOM		
Date 12.01.2024	Scale 1:200@A1 1:400@A3	Drawn AK	Checked AB	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1	Drawing Title PROPOSED KERBS, FOOTWAYS AND PAVED AREAS			
Drawing File Name NTA190002-NTA-PAV_HS-S04.1_XX_01-DR-KK-0004	Sheet Number 4 of 5	Status E3	Rev P03	



- LEGEND CONTINUED:**
- POROUS ASPHALT CYCLE TRACK, SMA 6 SURF PMB 65/100-60 DES SURFACE COURSE, DEPTH 30MM OVER, BINDER COURSE, AC20 40/60, DEPTH 60MM, 30mm 2/14mm CHOKER COURSE, 250mm 4/20mm CRUSHED CLEAN COARSE GRADED AGGREGATE, PER BS 7533-13, CONTRACTOR TO ALLOW FOR GEOTEXTILE AS PER APPENDIX 6/5
 - DEPOSITION OF 150mm CLASS 5A TOPSOIL AND GRASS SEEDING
 - PROPOSED IN SITU CONCRETE FOOTWAY / TRAFFIC ISLAND AND IN SITU CONCRETE KERB AND ISLAND / FOOTPATH TO BE CAST AS ONE. IN SITU CONCRETE SURFACE CLASS XF4 APPROX 100mm DEPTH, IN SITU CONCRETE KERB APPROX DEPTH 300mm, WIDTH 200mm, SUBBASE NRA SRW CLAUSE 808 (TII UGM AC) MATERIAL APPROX 150mm DEPTH AS PER, RM001 AND RM002 OF THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL
 - PROPOSED CONCRETE PAVING SLAB FOOTWAY APPROX 600X600X63mm CONCRETE PAVING SLAB, AND 3:1 SEMI-DRY SAND-CEMENT APPROX 30-50mm THICK AND APPROX. 100mm DEPTH, SUBBASE CEMENT BOUND MATERIAL CATEGORY 3 TO NRA SRW CLAUSE 1038, AS PER RM012 FOOTWAY DETAILS: CONCRETE PAVING SLABS, CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL
 - PROPOSED TACTILE PAVING, RED OR BUFF COLOURED AS INDICATED ON DRAWINGS, LAID ON APPROX. 30mm TO 70mm FIBRE REINFORCED SEMI-DRY CONCRETE, MINIMUM BEDDING COMPRESSIVE STRENGTH 35N/mm2, ON 150mm CLAUSE 808 (TII UGM AC), SURFACES SLOPING AT 10° OR LESS TO THE HORIZONTAL AS PER CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL IN ACCORDANCE WITH UK DOT GUIDANCE ON THE USE OF TACTILE PAVING SURFACES

- LEGEND:**
- PROPOSED EXTRUDED CONCRETE SEGREGATION KERB
 - PROPOSED IN-SITU CONCRETE KERB
 - PROPOSED IN-SITU CONCRETE DROPPED TRANSITION KERB
 - PROPOSED EDGING KERB AS PER
 - PROPOSED EXTRUDED 30 DEGREE SPLAY KERB WITH 60mm UPSTAND
 - PROPOSED GRANITE KERB, INTEGRATION OF NEW KERBS TO BE AGREED WITH DCC ON SITE.
 - PROPOSED GRANITE DROP KERB, INTEGRATION OF NEW GRANITE DROP KERBS TO BE AFREED WITH DCC ON SITE.
 - CYCLE RAMP MINIMUM 25mm OF 10mm DWC LAID ON 50mm OF 20mm DBM BS4987
 - CYCLE RAMP TO BE FORMED WITHIN POROUS ASPHALT CYCLE TRACK
 - PROPOSED PRECAST DRAINAGE CHANNEL TO BE PROVIDED AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0003'
 - PROPOSED TYPE A BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'
 - PROPOSED TYPE B BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'
 - PROPOSED TYPE C BOLLARD, AS PER 'NTA190002-NTA-SCD_ZZ-S04.1_XX_00-DR-KK-0001'

- TREE LEGEND:**
- TREE STEM
 - NOMINAL ROOT PROTECTION AREA (RPA)
 - ADJUSTED RPA

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

- NOTES:**
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TII SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST AGREE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - ALL DIMENSIONS TO BE CHECKED BY THE CONTRACTOR ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - EXISTING CARRIAGEWAY TO BE SAWCUT AND ADJOINED WITH PROPOSED KERBLINE.
 - HOT APPLIED SEALANT TO CLAUSE 1017.2 AND 1017.3 TO BE APPLIED AT ROAD PAVEMENT/KERB/CHANNEL INTERFACE.
 - PRIOR TO ANY WORKS ON HISTORIC PAVERS OR KERBS CATALOGUING AND TRAINING IS TO BE CARRIED OUT BY THE CONTRACTOR AS DIRECTED BY THE EMPLOYERS REPRESENTATIVE IN ACCORDANCE WITH THE WORKS REQUIREMENTS.

- FOR TENDER**

GENERAL NOTE:
GRANITE KERBS REMOVED IN CLEARANCE WORKS ARE TO BE REUSED ON SITE IN AGREEMENT WITH THE EMPLOYERS REPRESENTATIVE.
PAVING SLABS, PAVIOURS, SETTS, AND BLOCKS REMOVED IN CLEARANCE WORKS ARE TO BE REUSED ON SITE IN AGREEMENT WITH THE EMPLOYERS REPRESENTATIVE.

Disclaimer a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA. b. This drawing is to be used for the design element identified in the titleblock. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings. c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station. d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superseded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed. e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.	
--	---

TRS REF No.	LENGTH OF LINE (m)	LENGTH OF GAP (m)	WIDTH OF LINE (m)	COLOUR	KEY
RRM 001	CONTINUOUS	N/A	0.10	WHITE	
RRM 004	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				WHITE
RRM 008	CONTINUOUS	0.10	0.10	YELLOW	
RRM 016	PARKING BAYS AS PER 7.6.6 DOT TRAFFIC SIGNS MANUAL 2019				WHITE
RRM 017	CONTINUOUS	N/A	0.20	WHITE	
RRM 018C	0.30	0.30	0.10	WHITE	
RRM 021	HATCH MARKING AS PER FIG. 7.18 DOT TRAFFIC SIGNS MANUAL 2019				WHITE
RRM 022	CONTINUOUS	N/A	0.10	WHITE	
RRM 023	0.75	0.75	0.10	WHITE	
RRM 029	TAXI BAYS AS PER 7.6.13 DOT TRAFFIC SIGNS MANUAL 2019				
M 112	TRAFFIC CALMING SYMBOL AS PER SECTION 7.17 DOT TRAFFIC SIGNS MANUAL 2019				WHITE
M 115C	CYCLE TRACK YIELD AS PER SECTION 7.8 DOT TRAFFIC SIGNS MANUAL 2019				WHITE
M 116	CYCLE SYMBOL AS PER SECTION 7.8 DOT TRAFFIC SIGNS MANUAL 2019 (1200mm LENGTH x 750mm WIDTH EXCEPT WHERE STATED OTHERWISE)				WHITE
M 119	LANE DESTINATION AS PER CHAPTER 7.8 DOT TRAFFIC SIGNS MANUAL 2019				WHITE
M 124	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				WHITE
M 125	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				WHITE
M 126	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				WHITE
M 131	CONTINUOUS	N/A	0.10	WHITE	

SCHEDULE OF ROAD SIGNS									
P 010	BESPOKE INFORMATION PLATE "RAMPS" X-HEIGHT: 60mm	RUS. 058 450mm Dia	RUS. 020	RUS. 055 450mm Dia	RUS. 058CR 450mm Dia	RUS. 058CL 450mm Dia	RUS. 043 450mm Dia	F403 550mm WIDTH 1210mm HEIGHT	F350


Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the title block. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OS Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners, and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	01.05.2025	RD	AP	EG	ISSUED FOR TENDER

Client		Engineering Designer			
 Comhairle Cathrach Bhaile Átha Cliath Dublin City Council					
Date	01.05.2025	Scale	1:200@A1 1:400@A3	Drawn	RD
Project Code	NTA190002	Originator Code	NTA	Checked	AP
		QMS Code	S04.1	Approved	EG

Project Title			
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title			
PROPOSED TRAFFIC SIGNS AND ROAD MARKINGS			
Drawing File Name		Sheet Number	Status
NTA190002-NTA-TSM_RM-S04.1_XX_01-DR-KK-0003		3 of 5	E3
		Rev	
		P04	



NOTES:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
- EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
- ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
- DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
- ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
- CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
- WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE T11 SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST ASK THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
- SETTING OUT DETAILS TO BE AGREED WITH ENGINEER ON SITE.
- ALL ROAD MARKINGS & SIGNAGE TO BE IN ACCORDANCE WITH TRAFFIC SIGNS MANUAL (T.S.M.). T.S.M. REFERS TO THE "TRAFFIC SIGNS MANUAL" PRODUCED BY THE DEPARTMENT OF TRANSPORT 2019.
- ALL SIGNS TO BE INSTALLED ON A CRANKED POLE TO THE BACK OF FOOTPATH UNLESS OTHERWISE AGREED WITH ENGINEERS REPRESENTATIVE.
- TRAFFIC SIGNS TO BE INSTALLED IN SUCH A WAY AS TO ENSURE A LATERAL CLEARANCE OF 0.45M DISTANCE FROM THE OUTSIDE EDGE OF THE SIGN FACE TO THE ROADSIDE KERB.
- ALL TRAFFIC SIGNS TO BE MOUNTED ON POLES TO ENSURE A MINIMUM HEAD CLEARANCE OF 2.5M UNLESS SPECIFIED OTHERWISE.
- ALL ROAD WORKS INCLUDING ROAD MARKINGS AND SIGNS ARE TO BE REVIEWED ON SITE BY THE LOCAL AUTHORITY DEPARTMENTS PRIOR TO COMPLETION

LEGEND:


- PROPOSED NEW ROAD SIGN POST, NEW RETENTION SOCKET SYSTEM FOUNDATION, AND NEW SIGN FACE
- PROPOSED NEW SIGN FACE TO BE INSTALLED ON EXISTING LIGHTING COLUMN
- PROPOSED NEW ROAD SIGN POST, NEW RETENTION SOCKET SYSTEM FOUNDATION, AND RELOCATED SIGN FACE
- EXISTING SIGN POST AND SIGN PLATE TO BE TAKEN DOWN AND LATER REINSTATED
- PROPOSED FLEXIBLE KEEP RIGHT AND KEEP LEFT CYCLIST BOLLARD
- PROPOSED FLEXIBLE KEEP RIGHT BOLLARD

TREE LEGEND:

- TREE STEM
- NOMINAL ROOT PROTECTION AREA (RPA)
- ADJUSTED RPA

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER



SCHEDULE OF ROAD MARKINGS					
TRS REF No.	LENGTH OF LINE (m)	LENGTH OF GAP (m)	WIDTH OF LINE (m)	COLOUR	KEY
RRM 001	CONTINUOUS	N/A	0.10	WHITE	
RRM 004	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				
RRM 008	CONTINUOUS	0.10	0.10	YELLOW	
RRM 016	PARKING BAYS AS PER 7.6.6 DOT TRAFFIC SIGNS MANUAL 2019				
RRM 017	CONTINUOUS	N/A	0.20	WHITE	
RRM 018C	0.30	0.30	0.10	WHITE	
RRM 021	HATCH MARKING AS PER FIG. 7.18 DOT TRAFFIC SIGNS MANUAL 2019				
RRM 022	CONTINUOUS	N/A	0.10	WHITE	
RRM 023	0.75	0.75	0.10	WHITE	
RRM 029	TAXI BAYS AS PER 7.6.13 DOT TRAFFIC SIGNS MANUAL 2019				
M 112	TRAFFIC CALMING SYMBOL AS PER SECTION 7.17 DOT TRAFFIC SIGNS MANUAL 2019				
M 115C	CYCLE TRACK YIELD AS PER SECTION 7.8 DOT TRAFFIC SIGNS MANUAL 2019				
M 116	CYCLE SYMBOL AS PER SECTION 7.8 DOT TRAFFIC SIGNS MANUAL 2019 (1200mm LENGTH x 750mm WIDTH EXCEPT WHERE STATED OTHERWISE)				
M 119	LANE DESTINATION AS PER CHAPTER 7.8 DOT TRAFFIC SIGNS MANUAL 2019				
M 124	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				
M 125	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				
M 126	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				
M 131	CONTINUOUS	N/A	0.10	WHITE	

SCHEDULE OF ROAD SIGNS									
P 010	BESPOKE INFORMATION PLATE "RAMPS" X-HEIGHT: 60mm	RUS. 058 450mm Dia	RUS. 020	RUS. 055 450mm Dia	RUS. 058CR 450mm Dia	RUS. 058CL 450mm Dia	RUS. 043 450mm Dia	F403 550mm WIDTH 1210mm HEIGHT	F350

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the title block. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners, and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	01.05.2025	RD	AP	EG	ISSUED FOR TENDER

Client		Engineering Designer			
 Cornhairle Cathrach Bhaile Átha Cliath Dublin City Council					
Date	01.05.2025	Scale	1:200@A1 1:400@A3	Drawn	RD
Project Code	NTA190002	Originator Code	NTA	Checked	AP
				Approved	EG
				QMS Code	S04.1

Project Title			
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title			
PROPOSED TRAFFIC SIGNS AND ROAD MARKINGS			
Drawing File Name		Sheet Number	Status
NTA190002-NTA-TSM_RM-S04.1_XX_01-DR-KK-0004		4 of 5	E3
		Rev	
		P04	


- ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND
- NOTES:
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE TSI SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST ASSEE THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - SETTING OUT DETAILS TO BE AGREED WITH ENGINEER ON SITE.
 - ALL ROAD MARKINGS & SIGNAGE TO BE IN ACCORDANCE WITH TRAFFIC SIGNS MANUAL (T.S.M.). T.S.M REFERS TO THE "TRAFFIC SIGNS MANUAL" PRODUCED BY THE DEPARTMENT OF TRANSPORT 2019.
 - ALL SIGNS TO BE INSTALLED ON A CRANKED POLE TO THE BACK OF FOOTPATH UNLESS OTHERWISE AGREED WITH ENGINEERS REPRESENTATIVE.
 - TRAFFIC SIGNS TO BE INSTALLED IN SUCH A WAY AS TO ENSURE A LATERAL CLEARANCE OF 0.45M DISTANCE FROM THE OUTSIDE EDGE OF THE SIGN FACE TO THE ROADSIDE KERB.
 - ALL TRAFFIC SIGNS TO BE MOUNTED ON POLES TO ENSURE A MINIMUM HEAD CLEARANCE OF 2.5M UNLESS SPECIFIED OTHERWISE.
 - ALL ROAD WORKS INCLUDING ROAD MARKINGS AND SIGNS ARE TO BE REVIEWED ON SITE BY THE LOCAL AUTHORITY DEPARTMENTS PRIOR TO COMPLETION

- LEGEND:
- PROPOSED NEW ROAD SIGN POST, NEW RETENTION SOCKET SYSTEM FOUNDATION, AND NEW SIGN FACE
 - PROPOSED NEW SIGN FACE TO BE INSTALLED ON EXISTING LIGHTING COLUMN
 - PROPOSED NEW ROAD SIGN POST, NEW RETENTION SOCKET SYSTEM FOUNDATION, AND RELOCATED SIGN FACE
 - EXISTING SIGN POST AND SIGN PLATE TO BE TAKEN DOWN AND LATER REINSTATED
 - PROPOSED FLEXIBLE KEEP RIGHT AND KEEP LEFT CYCLIST BOLLARD
 - PROPOSED FLEXIBLE KEEP RIGHT BOLLARD

- TREE LEGEND:
- TREE STEM
 - NOMINAL ROOT PROTECTION AREA (RPA)
 - ADJUSTED RPA

AVAILABLE UTILITY INFORMATION SUGGESTS THE PRESENCE OF HIGH VOLTAGE CABLES, GAS MAINS AND OTHER UTILITY SERVICES IN THE WORKS AREA

FOR TENDER



SCHEDULE OF ROAD MARKINGS

TRS REF No.	LENGTH OF LINE (m)	LENGTH OF GAP (m)	WIDTH OF LINE (m)	COLOUR	KEY
RRM 001	CONTINUOUS	N/A	0.10	WHITE	
RRM 004	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				
RRM 008	CONTINUOUS	0.10	0.10	YELLOW	
RRM 016	PARKING BAYS AS PER 7.6.6 DOT TRAFFIC SIGNS MANUAL 2019				
RRM 017	CONTINUOUS	N/A	0.20	WHITE	
RRM 018C	0.30	0.30	0.10	WHITE	
RRM 021	HATCH MARKING AS PER FIG. 7.18 DOT TRAFFIC SIGNS MANUAL 2019				
RRM 022	CONTINUOUS	N/A	0.10	WHITE	
RRM 023	0.75	0.75	0.10	WHITE	
RRM 029	TAXI BAYS AS PER 7.6.13 DOT TRAFFIC SIGNS MANUAL 2019				
M 112	TRAFFIC CALMING SYMBOL AS PER SECTION 7.17 DOT TRAFFIC SIGNS MANUAL 2019				
M 115C	CYCLE TRACK YIELD AS PER SECTION 7.8 DOT TRAFFIC SIGNS MANUAL 2019				
M 116	CYCLE SYMBOL AS PER SECTION 7.8 DOT TRAFFIC SIGNS MANUAL 2019 (1200mm LENGTH x 750mm WIDTH EXCEPT WHERE STATED OTHERWISE)				
M 119	LANE DESTINATION AS PER CHAPTER 7.8 DOT TRAFFIC SIGNS MANUAL 2019				
M 124	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				
M 125	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				
M 126	LANE INDICATION ARROWS AS PER FIG. 7.24 DOE TRAFFIC SIGNS MANUAL 2019				
M 131	CONTINUOUS	N/A	0.10	WHITE	

SCHEDULE OF ROAD SIGNS

P 010	BESPOKE INFORMATION PLATE "RAMPS" X-HEIGHT: 60mm	RUS. 058 450mm Dia	RUS. 020 450mm Dia	RUS. 055 450mm Dia	RUS. 058CR 450mm Dia	RUS. 058CL 450mm Dia	RUS. 043 450mm Dia	F403 550mm WIDTH 1210mm HEIGHT	F350		

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titleblock. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken as to its accuracy, completeness, sufficiency or otherwise of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superseded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	01.05.2025	RD	AP	EG	ISSUED FOR TENDER

Client Comhairle Cathrach Bhaile Átha Cliath Dublin City Council		Engineering Designer AECOM		
Date 01.05.2025	Scale 1:200@A1 1:400@A3	Drawn RD	Checked AP	Approved EG
Project Code NTA190002	Originator Code NTA	QMS Code S04.1		

Project Title FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1	Drawing Title PROPOSED TRAFFIC SIGNS AND ROAD MARKINGS	Drawing File Name NTA190002-NTA-TSM_RM-S04.1_XX_01-DR-KK-0005	Sheet Number 5 of 5	Status E3	Rev P04
---	---	--	------------------------	--------------	------------

- ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND
- NOTES:
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - EMPLOYERS REPRESENTATIVE MUST BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE FROM THIS DRAWING. ANY MEASUREMENTS AND COORDINATES TO BE CONFIRMED ON SITE. LOCATIONS OF EXISTING SERVICES ARE INDICATIVE ONLY. THE CONTRACTOR MUST LIAISE WITH EACH UTILITY PROVIDER PRIOR TO THE COMMENCEMENT OF WORKS AND THROUGHOUT THE WORKS. THE CONTRACTOR IS TO PRESUME THAT ALL COMMUNICATION DUCTS CONTAIN FIBRE OPTIC CABLES.
 - ALL PROPOSED WORKS TO COMPLY WITH CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL.
 - CONTRACTOR TO DEVELOP THEIR TEMPORARY TRAFFIC MANAGEMENT PLAN FOR THE WORKS IN AGREEMENT WITH THE REQUIREMENTS OF DUBLIN CITY COUNCIL. THE TEMPORARY TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN EXISTING BUS ALIGNMENTS. EXISTING STOPS ALONG THE SCHEME SHOULD BE RETAINED, AND TEMPORARY STOPS BE PROVIDED WHERE THIS IS NOT POSSIBLE. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF 3 WEEKS NOTICE TO DUBLIN BUS BEFORE ANY STOPS ARE IMPACTED ALONG THE SCHEME.
 - WHERE REFERENCE TO NRA HAS BEEN MADE, THE CONTRACTOR IS TO REFER TO THE T1 SPECIFICATION FOR ROAD WORKS SERIES AND THE CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL. PRIOR TO ANY WORKS THE CONTRACTOR MUST ASK THE DETAIL PROPOSED WITH THE EMPLOYERS REPRESENTATIVE.
 - SETTING OUT DETAILS TO BE AGREED WITH ENGINEER ON SITE.
 - ALL ROAD MARKINGS & SIGNAGE TO BE IN ACCORDANCE WITH TRAFFIC SIGNS MANUAL (T.S.M.). T.S.M REFERS TO THE "TRAFFIC SIGNS MANUAL" PRODUCED BY THE DEPARTMENT OF TRANSPORT 2019.
 - ALL SIGNS TO BE INSTALLED ON A CRANKED POLE TO THE BACK OF FOOTPATH UNLESS OTHERWISE AGREED WITH ENGINEERS REPRESENTATIVE.
 - TRAFFIC SIGNS TO BE INSTALLED IN SUCH A WAY AS TO ENSURE A LATERAL CLEARANCE OF 0.45M DISTANCE FROM THE OUTSIDE EDGE OF THE SIGN FACE TO THE ROADSIDE KERB.
 - ALL TRAFFIC SIGNS TO BE MOUNTED ON POLES TO ENSURE A MINIMUM HEAD CLEARANCE OF 2.5M UNLESS SPECIFIED OTHERWISE.
 - ALL ROAD WORKS INCLUDING ROAD MARKINGS AND SIGNS ARE TO BE REVIEWED ON SITE BY THE LOCAL AUTHORITY DEPARTMENTS PRIOR TO COMPLETION



LEGEND:

-
-
-
-
-
-

TREE LEGEND:


-
-
-

DETAIL A - TYPICAL MASTIC IRONWORKS




SECTION E-E

DETAIL F - VERGE EDGING




DETAIL B - RM007 300mm GRANITE KERB

Typical Details




Plan




Section

DETAIL FROM CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL (2016)

DETAIL C - RM001 IN SITU CONCRETE FOOTWAY




Plan




Section

DETAIL FROM CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL (2016)

DETAIL D - RM008 BLOCK PAVING




Plan




Section

DETAIL FROM CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL (2016)

DETAIL E - RM012 CONCRETE PAVING SLABS




Plan




Section

DETAIL FROM CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL (2016)


DETAIL G - BOLLARD TYPE A, B, & C



DETAIL H - STEPPED CYCLE TRACK ARRANGEMENT




DETAIL I - SEGREGATION KERB



EXTRUDED SEGREGATION KERB

DETAIL R - SEGREGATION KERB DRAINAGE GAP



FOR TENDER

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Mean Head. All Co-ordinates are in Irish

Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drn	Chk'd	App'd	Description
P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
P04	28.04.2025	RD	AP	EG	ISSUED FOR TENDER


Client	Comhairle Cathrach Bhaile Átha Cliath Dublin City Council
Date	28.04.2025
Project Code	NTA190002
Scale	N.T.S@A1 N.T.S@A3
Originator Code	NTA

Engineering Designer	AECOM
Drawn	RD
Checked	AP
Approved	EG
QMS Code	S04.1


Project Title	FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1
Drawing Title	PROPOSED STANDARD DETAILS
Drawing File Name	NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0001
Sheet Number	1 of 3
Status	E3
Rev	P04

DO NOT SCALE USE FIGURED DIMENSIONS ONLY



DETAIL N - CYCLE RAMP





DETAIL O - CYCLE TURNING JUG



DETAIL P - FOOTPATH DRAINAGE CHANNEL




Asphalt Ramp



- NOTES :
- A. Existing concrete surface to be saw-cut as shown on drawing section 'A-A'.
 - B. Plane triangular profile and prime using bitumen.
 - C. Depths of tie-in may vary, see works requirement for full details.
 - D. 35mm of SMA 10 surf PMB 65/105.6 on bon dcoat to NRA CSW Clause 942.
 - E. 65mm AC20 heavy duty macadam basecourse with Grade 40/60 pen binder (HDM50) to NRA SRW Clause 929, on bond coat to Clause 920.

DETAIL Q - RM002 IN SITU CONCRETE KERB

Typical Details



DETAIL FROM CONSTRUCTION STANDARDS FOR ROAD AND STREET WORKS IN DUBLIN CITY COUNCIL (2016)

DETAIL R - ASPHALT RAMP

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish

Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drn	Chk'd	App'd	Description
P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER


Client	
Comhairle Cathrach Bhaile Átha Cliath Dublin City Council	
Date	Scale
12.01.2024	N.T.S@A1 N.T.S@A3
Project Code	Originator Code
NTA190002	NTA

Engineering Designer		
AECOM		
Drawn	Checked	Approved
AK	AB	EG
QMS Code	S04.1	


Project Title			
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title			
PROPOSED STANDARD DETAILS			
Drawing File Name	Sheet Number	Status	Rev
NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0003	3 of 3	E3	P03

FOR TENDER

DO NOT SCALE USE FIGURED DIMENSIONS ONLY



- ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND
- NOTES:
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - ALL DIMENSIONS TO BE CHECKED BY THE CONTRACTOR ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - EMPLOYERS REP TO BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - DIMENSIONS OF ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE. ALL MEASUREMENTS AND COORDINATES TO BE CHECKED ON SITE.
 - SPECIFIC CONSTRUCTION METHODOLOGY AND MATERIALS TO BE CONFIRMED BY CONTRACTOR.



SECTION A-A NTS @ A1


AVAILABLE UTILITY
INFORMATION SUGGESTS
THE PRESENCE OF HIGH
VOLTAGE CABLES, GAS
MAINS AND OTHER UTILITY
SERVICES IN THE WORKS
AREA

FOR TENDER

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish

Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners, and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drm	Chk'd	App'd	Description
P01	21.09.2023	RD	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER
RD	01.05.2025	RD	AP	EG	ISSUED FOR TENDER


Date	01.05.2025	Scale	N.T.S.@A1 N.T.S.@A3
Project Code	NTA19000	Originator Code	NTA

	Engineering Designer		
	AECOM		
S@A1 S@A3	Drawn RD	Checked AP	Approved EG
Code A	QMS Code S04.1		


Project Title	FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1
Drawing Title	PROPOSED BUILD OUT
Drawing File Name	NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0004
Sheet Number	1 of 1
Status	E3
Rev	P04

DO NOT SCALE USE FIGURED DIMENSIONS ONLY


Z:\UK\IEDBL\2\Jobs\IPR-426780_Cycling_Design_Office\900_CAD_GIS\IS04\911_1_WIP\DR\S04.1_Detailed Design\NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0007.dwg



PLAN VIEW



BASE



ISOMETRIC VIEW

ORDNANCE SURVEY IRELAND LICENCE NO CYAL50317588
©ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND

- NOTES:
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ENGINEERING DRAWINGS. ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE EMPLOYER.
 - ALL DIMENSIONS TO BE CHECKED BY THE CONTRACTOR ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - EMPLOYERS REP TO BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
 - DIMENSIONS OF ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 - DO NOT SCALE. ALL MEASUREMENTS AND COORDINATES TO BE CHECKED ON SITE.
 - SPECIFIC CONSTRUCTION METHODOLOGY AND MATERIALS TO BE CONFIRMED BY CONTRACTOR.

FOR TENDER

Disclaimer
a. © National Transport Authority (NTA) 2023. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number EN 0082119 National Transport Authority. All elevations are in metres and relate to OSI Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish

Transverse Mercator Grid (ITM) as defined by OSI active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus. The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superseded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.



Rev	Date	Drn	Chk'd	App'd	Description
P01	21.09.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P02	21.12.2023	GH	AB	EG	ISSUED FOR TENDER REVIEW
P03	12.01.2024	AK	AB	EG	ISSUED FOR TENDER

Client	
 Comhairle Cathrach Bhaile Átha Cliath Dublin City Council	
Date	12.01.2024
Project Code	NTA190002
Scale	N.T.S.@A1 N.T.S.@A3
Originator Code	NTA

Engineering Designer			
			
Drawn	AK	Checked	AB
Approved	EG		
QMS Code	S04.1		

Project Title			
FITZWILLIAM QUAY- LONDONBRIDGE STREET SECTION 1			
Drawing Title			
TRAFFIC CONTROLLER AND BASE DETAILS			
Drawing File Name	Sheet Number	Status	Rev
NTA190002-NTA-SCD_ZZ-S04.1_XX_01-DR-KK-0007	1 of 1	E3	P03

DO NOT SCALE USE FIGURED DIMENSIONS ONLY